

The Linearity of the Cosmic Expansion Field from 300 to 30,000 km s⁻¹ and the Bulk Motion of the Local Supercluster with Respect to the CMB

A. Sandage

*The Observatories of the Carnegie Institution of Washington,
813 Santa Barbara Street, Pasadena CA, 91101, USA*

B. Reindl and G. A. Tammann

*Department of Physics and Astronomy, Univ. of Basel,
Klingelbergstrasse 82, 4056 Basel, Switzerland*

g-a.tammann@unibas.ch

ABSTRACT

The meaning of “linear expansion” is explained. Particularly accurate *relative* distances are compiled and homogenized a) for 246 SNeIa and 35 clusters with $v < 30,000 \text{ km s}^{-1}$, and b) for relatively nearby galaxies with 176 TRGB and 30 Cepheid distances. The 487 objects define a tight Hubble diagram from 300 – 30,000 km s⁻¹ implying individual distance errors of $\lesssim 7.5\%$. Here the velocities are corrected for Virgocentric streaming (locally 220 km s⁻¹) and – if $v_{220} > 3500 \text{ km s}^{-1}$ – for a 495 km s⁻¹ motion of the Local Supercluster towards the warm CMB pole at $l = 275$, $b = 12$; local peculiar motions are averaged out by large numbers. A test for linear expansion shows that the corrected velocities increase with distance as predicted by a standard model with $q_0 = -0.55$ [corresponding to $(\Omega_M, \Omega_\Lambda) = (0.3, 0.7)$], but the same holds – due to the distance limitation of the present sample – for a range of models with q_0 between ~ 0.00 and -1.00 . For these models H_0 does not vary systematically by more than $\pm 2.3\%$ over the entire range. Local, distance-dependent variations are equally limited to 2.3% on average. In particular the proposed Hubble Bubble of Zehavi et al. and Jha et al. is rejected at the 4σ level. – Velocity residuals in function of the angle from the CMB pole yield a satisfactory apex velocity of $448 \pm 73 \text{ km s}^{-1}$ and a coherence radius of the Local Supercluster of $\sim 3500 \text{ km s}^{-1}$ ($\sim 56 \text{ Mpc}$), beyond which galaxies are seen on average at rest in co-moving coordinates with respect to the CMB. Since no obvious single accelerator of the Local Supercluster exists in the direction of the CMB dipole its motion must be due to the integral

gravitational force of all surrounding structures. Most of the gravitational dipole comes probably from within 5000 km s^{-1} .

Subject headings: cosmology: cosmological parameters — distance scale — cosmic microwave background — galaxies: distances and redshifts — kinematics and dynamics

1. INTRODUCTION

1.1. Preliminaries

The basic prediction of all models of ideal universes that are homogeneous and isotropic is that, if the expansion is real, there must necessarily be a linear relation between redshift and distance. There are many proofs, but among the earliest are those by Lemaître (1927, 1931) and Robertson (1928) even before the observational announcement by Hubble (1929) in which he, in the final sentence of his paper, suggested linearity may be only local.

Modern theoretical proofs for global linearity are set out in many of the standard text books at various levels of mathematical sophistication. Popular among the simpler proofs is that a linear relation is the only one that preserves relative shapes of geometrical shapes in an expanding manifold, and which is the same from all vantage points. Deeper proofs, based on properties of the metric of homogeneous, isotropic models, follow Robertson (1929, 1933) and Walker (1936), and lead to the Robertson-Walker line element of the metric.

A unique property of a linear velocity field is that every vantage point in the field appears to be the center of the expansion and has the same ratio of velocity to distance over the entire field. Because of this important property, much effort over the past 80 years has been made by the observers to prove, or disprove, linearity, either locally or globally. The first comprehensive result was that by Hubble & Humason (1931), enlarging the observational data available to Hubble in 1929.

Many summaries of the theoretical expectation of linearity and observational verification for the standard model exist. From the theoretical side the classic text books include those by Heckmann (1942), Bondi (1960), Robertson & Noonan (1968), Harrison (1981), Narlikar (1983), Peebles (1993), Peacock (1999). Bowers & Deeming (1984), and Carroll & Ostlie (1996) are exemplary at the high end of the intermediate level. On the observational side, text book-like chapters by Gunn & Oke (1975) and Sandage (1975, 1988, 1995) are useful.

Deviations from a linear velocity-distance relation divide into two categories. (1) The

relation is non-linear everywhere, i.e. the deviation is global. (2) The deviation is local, going over into a linear relation at large distances.

The first category is the most fundamental because it denies the standard homogeneous model everywhere. The second contains models where either the local Hubble constant changes up to a certain distance such as increasing or decreasing outward, or where the local irregularities are due to streaming motions due, presumably, to a local inhomogeneous distribution of matter.

The most radical of the first category of global non-linear models can easily be disproved observationally, even as early as in Hubble & Humason (1931), by noting that the slope of the local $\log(\text{redshift})$ - magnitude relation is close to 0.2 as expected in the case of linear expansion. This conclusion was much strengthened by the tight Hubble diagram from brightest clusters galaxies in Humason et al. (1956) and then, from 1972 to 1975, by a series of papers on the velocity-distance relation based on new redshifts and apparent magnitudes of galaxy clusters measured at Mount Wilson and Palomar (Sandage 1999, Table 1 for a summary).

Non-linear models in the second category are more difficult to disprove because the deviations from the pure Hubble linear flow are much smaller than in the radical first group and can easily be mocked by systematic distance errors due to bias effects. The literature is large on deviations from a pure Hubble flow, either due to local streaming motions or to a variation of the Hubble constant outward, or to a local bulk motion relative to a globally significant distant kinematic frame. Some are easier to disprove than others.

One such non-linear model assumes that the local global distribution of matter is hierarchical. Following Charlier (1908, 1922) and using a suggestion by Carpenter (1938) of a density-size relation for all objects in the universe, de Vaucouleurs (1970, 1971) postulated a universe made of hierarchies of decreasing mean density with increasing volume size up to some limiting distance. The velocity-distance relation in such a universe was formulated by Haggerty (1970), and Haggerty & Wertz (1971), following a prediction of Wertz (1970), and was found to be nearly quadratic locally, but becoming linear at large distances. The model was shown, however, to be irreconcilable with observations (Sandage, Tammann, & Hardy 1972).

It was early demonstrated (e.g. Sandage & Tammann 1975; Teerikorpi 1975a,b, 1984, 1987; Fall & Jones 1976; Bottinelli et al. 1986, 1987, 1988; Sandage 1988, 1994; Federspiel et al. 1994) that the claimed changes of the Hubble constant outward were often caused by

uncorrected observational selection bias (see also Sandage 1994, 1995, Chapter 10).¹ It must also be stated that in the early papers some of the claimed distortions of the velocity field were due to the omission of velocity corrections for Virgocentric infall and – for the more distant galaxies – for CMB dipole motion.

Hence, despite many papers and conferences on proposed streaming motions and searches for variations of the Hubble constant with distance, the problem is still open. What has been needed are distance indicators that have very small intrinsic dispersion so as to eliminate, or greatly reduce, the effect of distance-dependent incompleteness selection bias. At small distances the increasing number of Cepheid and TRGB distances becomes most helpful here, whereas for large distances Type Ia supernovae at maximum light have emerged as the best standard candles, just as Zwicky (1962) had proposed.

1.2. The Complications: The Invisible World Map Must be Inferred from the Visible World Picture

The concept of linearity of a velocity-distance velocity field, so simple to describe, is most complicated to define properly in an expanding universe. Milne (1935) proposed language that clarifies the problem. Robertson (1955) also uses the same language.

The problems are these.

(1) Because we do not observe the universe at large redshift at the same cosmic time as at low redshift, we must distinguish between what Milne called the world map and the world picture. The world map is the state of the universe at a given cosmic time. The world picture is what appears to us. We cut the series of world maps at different cosmic times as we look to different redshifts.

By a linear “velocity”-“distance” relation is meant that at a particular cosmic time there is a linear relation in the world map between the coordinate distance as measured by the metric, and redshift. But the metric distance, $R(t)r$, where $R(t)$ is the time dependent expansion scale factor and r is the invariant (constant for all time) comoving radial metric

¹It is important to emphasize that bias of this nature is *not* the famous Malmquist bias, but rather is an incompleteness bias that increases with distance. In contrast, the Malmquist bias is distance independent. It only concerns the error made in assigning a number to an absolute magnitude calibration of a distance indicator when using a sample that is magnitude, rather than, distance limited. On the other hand, an incompleteness bias causes an error that increases with distance, which, if uncorrected, makes the Hubble constant appear to increase outward with distance. The error of calling the incompleteness bias as Malmquist is wide spread in the literature.

“distance”. It is not the same as a distance measured by an astronomer using observational data. There are many kinds of such “astronomical” distances, depending on the method by which they are measured. There is the distance when light left a galaxy, the distance when light is received, the luminosity distance by apparent magnitude, the distance by angular size, the round-trip distance by radar signals. All differ at large redshifts, and are the same only in the zero redshift limit. McVittie’s (1974) discussion is useful here. Which distance do we use in formulating a velocity-“distance” relation and proving that it is “linear”?

There is also the difficulty with “velocity”. What we measure is redshift, not velocity. The two are not the same except, again, in the zero redshift limit (Harrison 1993).

The problem is solved by not using the complicated concepts of velocity and distance but by transforming the world map into the observer’s world picture *using only observables*. Before 1958 this mapping was done by making a Taylor series expansion of the $R(t)$ expansion factor about the present cosmic time so as to sample the world map at the earlier cosmic times (Robertson 1955). This could be called a tangent mapping, and is not very useful for redshifts larger than those at moderately local distances. What was needed was a general transformation mapping that is valid for all redshifts.

Mattig (1958) solved the problem with his famous equation that relates the metric distance of a galaxy, $R_0 r$, at the time of light reception with the redshift, no matter how large, in models with zero cosmological constant. Metric distance is further replaced by apparent magnitude by the Robertson (1938) equation that connects the two. In addition to the apparent magnitude and the redshift the equation contains the Robertson (1955) deceleration parameter, $q_0 = -R_0 \ddot{R} / \dot{R}^2$, which, in the simplest models with no cosmological constant, is determined by the mean matter density of the model. In that case the values of H_0 and q_0 observed at the present epoch are used to parametrize the past and the future of the world map.

The Mattig equation, or more complicated versions for models that incorporate the cosmological constant (e.g. Mattig 1959; Carroll et al. 1992) which we use in the next section, provides the connection between the world map and the world picture. It has properly been said that the Mattig equation is “one of the single most useful equations in cosmology as far as observers are concerned” (Peacock 1999, p. 89). Mattig’s solution began the modern era of practical observational cosmology and has been used for many auxiliary and related problems concerning such observational data as galaxy counts, angular diameters, and others throughout the past 50 years.

Because the world map defined in the Robertson-Walker metric has a well defined linear relation between coordinate (metric) distance and redshift, and because a Mattig-like

equation transforms the map in to the observed picture, the test for linearity becomes one of comparing the observed redshifts at a given apparent magnitude with the predicted redshifts from a model. The linearity test becomes, then, a search for residuals in the subtraction of the redshifts predicted *from the model* from the observed redshifts at a given photometric distance obtained from the observations as $(m - M)$. Streaming motions and/or variations of the Hubble constant outward are searched for as correlations (or not) of the residuals with direction and photometric distance.

The test for linearity is, then, model-dependent: we must compare the observed redshift-magnitude relation with the prediction for some adopted world model as it is transformed into the world picture by a Mattig-like equation of $(m - M) = f(z, q_0, \Lambda)$. We can only test linearity relative to the adopted model. We test for the sensitivity to the adopted model in § 3.

1.3. This Paper

The purpose of this paper is: (1) To test the linearity of the local expansion field within $z < 0.1$. Beyond this limit the linearity of the expansion of space is well documented out to $z = 0.4$ by the SNe Ia of Hicken et al. (2009), which have ample overlap with the present data, and which can be tightly fit to the SNe Ia compiled by Kessler et al. (2009) extending to $z > 1$. The high- z data are essential to optimize the determination of the world model for which linear expansion is valid. But at smaller distances the character of the expansion field is still poorly known because so far the number of objects with sufficiently accurate distances has been small. Yet the test is important to understand the effect of the observed clumping of visible matter on the local dynamics. It is also important to find the minimum distance at which the cosmic value of H_0 can be found independent of peculiar velocities. Strong local deviations from linearity have in fact frequently been claimed up to the recent past by Zehavi et al. (1998) and Riess et al. (2009). (2) To determine the size of the comoving volume that partakes of our observed velocity relative to the dipole of the CMB.

The plan of the paper is this. In § 2 the data are specified. In § 2.1 accurate *relative* distances of 246 SNe Ia and 35 clusters within the adopted distance range are compiled from eight different sources. The distances have demonstrably rms errors of ≤ 0.18 mag; only relative distances are needed in the present context. The distances on an arbitrary zero point, reduced to the barycenter of the Local Group, are listed in Table 1 together with the appropriate velocities v_{hel} , v_{220} (corrected for Virgocentric infall), and v_{CMB} (corrected for motion with respect of the CMB dipole A_{corr} if $v_{220} > 3500 \text{ km s}^{-1}$). In § 2.2 30 Cepheid and 176 TRGB distances which are equally accurate as those of SNe Ia are added in order

to extend the sample down to 300 km s^{-1} . They are reduced to the barycenter of the Local Group and corrected for the Virgocentric flow as in § 2.1. We justify in § 2.3 why other distance indicators are not considered here.

In § 3 the problem of linear expansion is set out. The actual test in § 3.1 uses a Hubble diagram of *all* objects in the sample and analyzes the residuals from a Hubble line for a standard Λ CDM model with $\Omega_M = 0.3$ and $\Omega_\Lambda = 0.7$. (Note that this model implies a deceleration parameter of $q_0 = -0.55$ because it holds that $q_0 = 0.5(\Omega_M - 2\Omega_\Lambda)$ for all Friedmann models [e.g. Sahni & Starobinsky 2000]). § 3.2 explores the dependence of linearity on the adopted model in terms of q_0 .

An analysis of the velocity residuals of objects with $v_{220} < 7000 \text{ km s}^{-1}$ (the limit is set to avoid an overwhelming effect of distance errors) in function of direction is in § 4, showing the size of the Local Supercluster and its motion toward A_{corr} , which is the direction of the warm pole of the CMB after correction for our Virgocentric velocity vector.

Results and conclusions are in § 5.

2. THE DATA

In order to trace the local expansion field the *most accurate relative* distances are compiled of objects, comprising SNe Ia, clusters, Cepheids, and tip of the red-giant branch (TRGB) distances, with velocities from 300 to 30,000 km s^{-1} .

All quoted distances are reduced to the barycenter of the Local Group (LG) which is assumed to lie on the line between the Galaxy and M31 and at a distance of one third of $(m - M)_{\text{M31}}$. The small random error of the distance moduli (0.15 mag on average as shown below) makes the samples unusually insensitive to incompleteness bias.

Heliocentric velocities v_{hel} are available for all objects. They are reduced here to the barycenter of the LG following Yahil et al. (1977). The resulting velocities, v_{LG} , are then corrected for a self-consistent Virgocentric infall model by Δv_{220} which is the vector sum of the $220(\pm \sim 30) \text{ km s}^{-1}$ infall vector at the position of the LG, (Peebles 1976, 1980; Yahil et al. 1980a; Hoffman et al. 1980; Tonry & Davis 1981; Dressler 1984; Yahil 1985; Tammann & Sandage 1985; Kraan-Korteweg 1986; de Freitas Pacheco 1986; Giraud 1990; Jerjen & Tammann 1993) and the infall velocity of a particular object, both projected onto the line of sight between the observer and the object. The center of the Virgo cluster is taken to coincide with NGC 4486 at $l = 283.8$, $b = 74.5$. The infall vectors scale with Virgocentric distance r_{Virgo} like $1/r_{\text{Virgo}}$ if a density profile of the Local Supercluster of $\rho \sim r^{-2}$ is assumed

(Yahil et al. 1980b). Since good (relative) distances are known for all objects including the Virgo cluster, the corrections Δv_{220} can be calculated from equation (5) in Sandage et al. (2006). The velocities $v_{220} = v_{\text{LG}} - \Delta v_{220}$ would be observed in the absence of any streaming towards the Virgo cluster center and if the infall model were exact, but deviation from the model (see e.g. Klypin et al. 2003) will add to the true peculiar velocities of local galaxies. The velocities v_{CMB} of only the objects with $v_{220} > 3500 \text{ km s}^{-1}$ are in addition corrected by $\Delta v_{\text{CMB}} = v_{220} - 495 \cos \alpha \text{ km s}^{-1}$ (α being the angle from the CMB apex A_{corr} to compensate for the reflex of the Local Supercluster motion relative to the CMB [see § 4]).

2.1. SNe Ia and Cluster Distances

Eight published sets of accurate relative distances that contain more than 10 SNe Ia or clusters are considered here.

Six sets are based on SNe Ia. Since SNe Ia are treated as standard candles it makes no difference whether their distance measures are published as corrected apparent magnitudes at maximum or as distance moduli. In either case the data are converted to “true” distance moduli by forcing each data set to give the same fixed mean value of H_0 . We have chosen here $H_0 = 62.3 \text{ [km s}^{-1} \text{ Mpc}^{-1}]$ as found from Cepheid-calibrated SNe Ia (Sandage et al. 2006; Tammann et al. 2008b). As mentioned before the absolute calibration is not necessary for the present investigation, but a realistic calibration will simplify some of the following discussions.

Two sets of relative cluster distances expressed in km s^{-1} yield equally tight Hubble diagrams as SNe Ia. This is thanks to the large number of galaxy distances determined in each cluster. The mean cluster distances are normalized to the same fiducial value of H_0 .

The objects in each data set are separately plotted in Hubble diagrams $\log v_{220/\text{CMB}}$ vs. $(m - M)$ in Figure 1a-g. The Hubble line shown holds for the adopted Λ CDM model with $\Omega_{\text{M}} = 0.3$, $\Omega_{\Lambda} = 0.7$ and is defined by (Carroll et al. 1992)

$$(m - M) = 5 \log c(1 + z_1) \int_0^{z_1} [(1 + z)^2(1 + \Omega_{\text{M}}z) - \Omega_{\Lambda}z(2 + z)]^{-1/2} dz + 25 - 5 \log H_0. \quad (1)$$

The scatter about the Hubble line ($0.13 - 0.18 \text{ mag}$) is shown in each panel. The values refer to the velocity range of $3000 < v_{220/\text{CMB}} < 20,000 \text{ km s}^{-1}$ where they are least affected by peculiar motions, K -corrections, and photometry at faint levels.

The sources of the eight samples – all normalized here to the fiducial value of H_0 – are detailed in the following:

(1) Maximum magnitudes m_V^{corr} are available for 105 Type Ia supernovae (SNIa) (62 of which fall into the fiducial range $3000 < v_{220/\text{CMB}} < 20,000 \text{ km s}^{-1}$) from Reindl et al. (2005), excluding spectroscopically peculiar objects of type SN 1991T and 1991bg. They have been corrected for Galactic and internal absorption and homogenized as to decline rate and intrinsic color. The corresponding distances yield the Hubble diagram in Figure 1a.

(2) Wang et al. (2006) give corrected distance moduli based on maximum $UBVI$ magnitudes and some adopted standard luminosity of 98 SNe Ia (55 of which fall into the fiducial velocity range). The magnitudes are corrected for absorption and homogenized as to decline rate and color index with somewhat different precepts as under (1). Their published SN magnitudes are brighter than in (1) because the intrinsic color of SNe Ia was assumed to be improbably blue causing large absorption corrections, but this does not disturb the internal consistency of the data. The data give the Hubble diagram in Figure 1b.

(3) Jha et al. (2007) have derived homogenized, absorption-corrected maximum V magnitudes of 95 SNe Ia (72 of which fall into the fiducial velocity range) by fitting multi-color light curves to templates. The SNe Ia are plotted in Figure 1c.

(4) Maximum H magnitudes of 33 SNe Ia (of which 26 fall into the fiducial velocity range) have been published by Wood-Vasey et al. (2008). They provide, *without* any homogenization for decline rate or color and with only insignificant absorption corrections, the Hubble diagram shown in Figure 1d.

(5) Maximum I magnitudes, corrected for absorption and decline rate, for 21 SNe Ia (of which 19 fall into the fiducial velocity range) have been published by Freedman et al. (2009). The data have been added in Figure 1d.

(6) Hicken et al. (2009) have reduced SN data for a very large sample of SNe Ia in four different ways. Two methods follow Guy et al. (2005, 2007) and two methods follow the multi-color light curve fitting of Jha et al. (2007) with two different assumptions on the absorption-to-reddening ratio for SNe Ia ($R_V = 3.1$ and 1.7). The authors give distance moduli for all four cases on the assumption of $H_0 = 65$. We have selected the 91 SNe Ia of 2001 and later in the range of $3000 < \log v_{220/\text{CMB}} < 20,000 \text{ km s}^{-1}$ for which we could find the parent galaxy, position, and a sufficiently accurate redshift in the NASA/IPAC Extragalactic Database (NED).² For two SNe Ia (2002es and 2007qe) the available redshifts are discrepant; they are left out as well as the two deviating SNe Ia (2002jy and 2007bz) leaving 87 SNe Ia. Their Hubble diagrams based on the reduction methods of Guy et al. have significantly larger scatter ($\sigma_{(m-M)} = 0.23$) than those following the method of Jha

²See <http://nedwww.ipac.caltech.edu>.

et al. We have adopted therefore the latter taking the mean of the moduli from $R_V = 3.1$ and 1.7. These means, normalized to the present distance scale, are used to construct the Hubble diagram in Figure 1e.

(7) Masters et al. (2006) have derived relative mean cluster distances (in km s^{-1}) from 21cm line width distances of 26 member galaxies per cluster on average. Their sample of 31 clusters defines a tight Hubble diagram with the exception of the three nearest clusters (not shown) whose relative distances have been measured too large (see Tammann et al. 2008a). The reason for the discrepancy, seen already in the preceding work of Giovanelli et al. (1999), is not understood; it is apparently not possible to apply the same selection criteria for cluster members in nearby and distant clusters. The remaining 28 cluster distances, normalized as before, are shown in Figure 1f.

(8) Jørgensen et al. (1996) have determined relative distances (in km s^{-1}) of 10 clusters by averaging Fundamental Plane (FP) distances of about 23 galaxies per cluster. The sample is small, but it provides one of the few (relative) distance determinations of the Coma cluster. The Hubble diagram with the normalized cluster distances is in Figure 1g.

The sources (1)–(8) contain 502 entries for 246 different SNe Ia and 35 clusters and groups. The distance of objects with more than one entry have been averaged. The relevant parameters of the 281 objects are listed in Table 1.

The columns that need explanation are these: Columns (4) and (5) are the Galactic coordinates. Columns (6), (7), and (8) are the velocities relative to the Sun taken from the NED (Col. 6), the velocities v_{220} corrected for the self-consistent Virgocentric infall model (Col. 7), and – in case $v_{220} > 3500 \text{ km s}^{-1}$ – the velocities v_{CMB} corrected to the inertial frame of the CMB as explained above (Col. 8). Column (9) is the distance modulus with the zero-point set as before by $H_0 = 62.3$. Note that the moduli are given relative to the barycenter of the LG. Column (10) is the angle in degrees from the adopted CMB apex A_{corr} . Column (11) is the difference Δv_{220} between the velocity v_{220} and the model velocity v_{model} predicted by equation (1) using the adopted distance moduli from Column (9). Column (12) gives the key to the original sources. 1: Reindl et al. (2005); 2: Wang et al. (2006); 3: Jha et al. (2007); 4a: Wood-Vasey et al. (2008); 4b: Freedman et al. (2009); 5: Hicken et al. (2009); 6: Masters et al. (2006); 7: Jørgensen et al. (1996).

The 281 *mean* distances in Table 1 define the Hubble diagram in Figure 1h. The subset of 218 objects which fall into the interval $3000 < v_{220/\text{CMB}} < 20,000 \text{ km s}^{-1}$ scatter about the Hubble line by $\sigma_{(m-M)} = 0.15 \text{ mag}$, which must be due in part to distance errors and to peculiar velocities.

The systematic distance difference of those SNe Ia occurring in at least two of the above

sources is zero by construction. Their mean random differences are given in Table 2. The overall average difference is 0.15 mag which implies a mean error of a single distance determination of ~ 0.10 mag. If this value is subtracted in quadrature from the scatter of 0.15 mag observed in Figure 1h one is left with an error, read in velocity, of $\sigma_{\log \Delta v} = 0.022$ or 5%, which corresponds to a radial velocity dispersion of 250 km s^{-1} at $v_{\text{CMB}} = 5000 \text{ km s}^{-1}$ and 430 km s^{-1} in three dimensions. The value compares well with the peculiar velocity of the Local Supercluster of 495 km s^{-1} toward the CMB apex A_{corr} (see § 4).

It is central to this paper to note that the free-fit *linear* regressions in the Hubble diagrams of Figure 1a-h in the well occupied range of $3000 < v_{220/\text{CMB}} < 20,000 \text{ km s}^{-1}$, with the slopes set out in Table 3, are flatter than the canonical value of 0.2 in six out of seven cases; the mean slope is flatter by 3.5σ . The reason concerns the difference between the world picture seen in the data and the world map as derived by the Mattig (1958) transformation between them to be described in § 3.

2.2. The Extension of the Hubble Diagram to Smaller Distances

2.2.1. Cepheids

The uniformly reduced Cepheid distances of 30 galaxies with $(m - M) > 28.2$ were compiled in Tammann et al. (2008b). They are, after exclusion of the deviating NGC 3627, plotted in Figure 2 where also the objects of Figure 1h are repeated.

The Cepheids can be added directly to the Hubble diagram of SNe Ia and clusters, because they all share the same zero point of the distance scale. This is by construction, because 10 of the Cepheid distances were used in Sandage et al. (2006) as the only luminosity calibrators of SNe Ia. The agreement is confirmed by the statistical equality of H_0 from only the 29 Cepheids (63.4 ± 1.8) by Tammann et al. (2008b) and the value derived from the SNe Ia (62.3 ± 1.3) by Sandage et al. (2006).

2.2.2. TRGB distances

The 78, through RR Lyr stars *independently* calibrated TRGB distances with $(m - M) > 28.2$ yield a quite local value of $H_0 = 62.9 \pm 1.6$ (Tammann et al. 2008b). The close agreement of this value with the fiducial value of 62.3 is taken as justification to plot all 176 TRGB distances outside the LG into Figure 2 without any additional normalization. The combination of the SNe Ia and clusters in § 2.1 with the Cepheids and TRGB distances here

defines the Hubble line in Figure 2 from the lowest recession velocities up to $30,000 \text{ km s}^{-1}$.

It could be objected that the fit of the galaxies with TRGB distances to the more distant objects depended solely on the similarity of the respective values of H_0 , but that the agreement was only the product of chance. Proponents of a high large-scale value of $H_0 > 70$ are actually forced to argue in this way. To answer this objection we have fitted separately the Hubble lines of the TRGB objects and that of the Cepheids and SNeIa in the region of overlap, i.e. $28.2 < (m - M) < 31.5$. (The lower limit is chosen as elsewhere in this paper to avoid a dominant effect of peculiar velocities). The 29 Cepheids and 19 SNe in this interval fix the intercept of the Hubble line to within $\Delta \log v = \pm 0.012$ and the 78 TRGB distances in the same interval to within ± 0.011 . Joining the two samples leaves therefore an uncertainty of $\Delta \log v = \pm 0.016$, corresponding to a distance margin of $\Delta(m - M) = \pm 0.08$ (or 4% in linear distance). Without taken regress to the actual value of H_0 , the change of H_0 between the very local value from TRGB distances and the value on larger scales from Cepheids and SNeIa can therefore be limited to $\pm 4\%$ (1σ).

2.3. Other Hubble Diagrams of Field Galaxies and Clusters

Different methods to determine the distances of field galaxies have been applied to map the velocity field. They are struck by random distance errors of $> 0.3 \text{ mag}$ (except field galaxies with SNeIa) which causes severe statistical problems unless one has complete (or fair) *distance-limited* samples. Since it is not possible to define such samples much beyond 1000 km s^{-1} the methods have been applied to *apparent-magnitude-limited samples*. In this case the less luminous galaxies are increasingly discriminated against as one progresses to larger distances. The result is that the mean luminosity of the catalogued galaxies increases with distance (incompleteness bias). If this effect is not allowed for one derives a compressed distance scale with H_0 seemingly increasing with distance. This then can lead to spurious peculiar velocities and galaxy streamings. Of course other reasons for distance-dependent biases exist, e.g. if the distance indicator depends on resolution or if it depends on galaxy size. In all cases deviations from linear expansion increasing systematically with distance are a sign of some kind of bias.

The problem of bias in the presence of large scatter is discussed for the following four examples.

2.3.1. The Hubble diagram from 21cm and optical line width distances of spirals

A Hubble diagram of a complete *distance*-limited sample of 104 field galaxies, yet extending out to only $v_{220} = 1000 \text{ km s}^{-1}$, has been constructed with 21cm line width distances (Tammann et al. 2008b, Fig. 3a). The slope of the Hubble line is consistent with 0.2, but the very large scatter of $\sigma_{(m-M)} = 0.69 \text{ mag}$ – much too large to be caused by peculiar velocities – prevents a rigorous test for linear expansion. Also an early *magnitude*-limited sample of 217 field galaxies has been presented by Aaronson et al. (1982). Combining 21cm line widths with H magnitudes they have derived distances which – if cut at $v_{220} < 2500 \text{ km s}^{-1}$ – define a Hubble line consistent with a slope of 0.2, but the error is substantial due to the large scatter.

Federspiel et al. (1994) have analyzed a magnitude-limited sample of 1355 galaxies out to $\sim 10,000 \text{ km s}^{-1}$ for which Mathewson et al. (1992) have collected 21cm *and* optical line widths and corrected I magnitudes. The galaxies, lying in two fields towards and perpendicular to the Great Attractor, define Hubble diagrams with dispersions of 0.4 – 0.7 mag depending on line width, and which clearly reveal incompleteness bias by producing slopes significantly larger than 0.2. On the assumption of linear expansion the bias has been corrected out by means of so-called Spaenhauer-diagrams. The corrected distances show a local velocity anomaly in the direction of the Great Attractor of 500 km s^{-1} which, however, levels off at a distance of 4000 km s^{-1} . The conclusion was that there is no streaming extending to the Great Attractor at $v \sim 4500 \text{ km s}^{-1}$.

In order to beat the large intrinsic dispersion of line width distances and the accompanying incompleteness bias very large all-sky samples of several thousand field and cluster galaxies have been studied (Springob et al. 2007, 2009; Theureau et al. 2007) and will be further increased in the future (Masters 2008).

2.3.2. Hubble diagrams from $D_n - \sigma$ and FP distances of early-type galaxies

Faber et al. (1989) have derived $D_n - \sigma$ distances (in km s^{-1}) of 317 E and S0 galaxies out to $\sim 10,000 \text{ km s}^{-1}$. The corresponding Hubble diagram has a scatter of $\sigma_{(m-M)} = 0.69 \text{ mag}$, which is reduced to $\sigma_{(m-M)} = 0.50 \text{ mag}$ by correcting for what the authors call “Malmquist correction”, but which is actually a correction for the population size of the aggregate from which a galaxy is drawn. In their Table 4 they list *mean* distances of 59 clusters and groups and distances of 58 single galaxies which define the Hubble diagram shown in Figure 3. The scatter is still large (0.48 mag) and the slope (0.187 ± 0.07) is flatter than the expected value of 0.2. This implies that if H_0 is assumed to be 62.3 at $(m - M) = 31.5$ it decreases to

$H_0 = 56.1$ at $(m - M) = 35.0$. The decrease of H_0 is contrary to what is expected from an incompleteness bias; it may be that the specific “Malmquist correction” of the authors leads to an overcorrection of the distances.

All of Faber’s et al. (1989) galaxy distances were analyzed in a number of publications some of which preceded the paper by Faber et al. (e.g. Dressler 1987; Faber & Burstein 1988; Lynden-Bell et al. 1988; Faber et al. 1988; Burstein 1990). The authors, taking the distances at face value, concluded that a coherent large-scale influx existed into a group of galaxy clusters centered on Abell 3627, called the “Great Attractor”, at a distance of $\sim 4500 \text{ km s}^{-1}$, whose dominant attraction would be the main cause for the Local Group’s motion with respect to the CMB. – First doubts about the rôle of the “Centaurus Concentration” (synonymous for Great Attractor) came from Lynden-Bell et al. (1989), who concluded from the optical dipole from galaxy catalogs that most of the Local Group’s motion is caused from within 3500 km s^{-1} and that the more distant cluster concentration about Abell 3627 was only a minor contributor. Additional evidence for this view is given in § 5.

Mean Fundamental Plane (FP) distances of 85 clusters with $v_{\text{CMB}} = 5000\text{--}20,000 \text{ km s}^{-1}$ have also been derived by Colless et al. (2001), but they are based on average on only ~ 5 cluster members. The resulting Hubble diagram has a large scatter of $\sigma_{(m-M)} = 0.34 \text{ mag}$ and the Hubble line has too flat a slope (0.165). For these reasons the data have not been used for the linearity test.

Forthcoming bias-corrected FP distances of up to $\gtrsim 10,000$ galaxies in the Southern sky are announced (Smith et al. 2004; Jones et al. 2004; Springob et al. 2010); they shall serve to map the velocity field of the local universe out to $\lesssim 20,000 \text{ km s}^{-1}$.

2.3.3. *The Hubble diagram from surface brightness fluctuation (SBF) distances*

SBF distances of 124 mainly E and S0 galaxies have been published by Tonry et al. (2001). Their Hubble diagram is shown in Figure 4. The scatter of $\sigma_{(m-M)} = 0.43 \text{ mag}$ is large; even for this relatively nearby sample ($v_{220}(\text{median}) = 1626 \text{ km s}^{-1}$) only part of the scatter can be attributed to peculiar motions. Yet the most striking is the steepness of the Hubble line with slope 0.233; it implies values of $H_0 = 62.5$ at $(m - M) = 30.00$ and of $H_0 = 78.7$ at $(m - M) = 33.00$. The seeming non-linearity of the expansion field is impossible and must be due to some bias of the data, which may be caused by a selection effect depending on apparent-magnitude (incompleteness bias) or some other distance-dependent bias of this sensitive method (perhaps due to incomplete removal of non-stellar images). The consequence is that the method should not be used to test the character of the expansion

field nor for the determination of reliable galaxy distances.

2.3.4. *The Hubble diagram of planetary nebula (PNLF) distances*

Galaxy distances derived from the bright tail of the luminosity function of the shells of planetary nebulae in the light of the $\lambda 5007 \text{ \AA}$ line have been compiled from Ciardullo et al. (2002), Feldmeier et al. (2007), Herrmann et al. (2008), and the NED. Of the resulting galaxies 46 lie outside the LG. They define a Hubble diagram as shown in Figure 5. A free fit through the 36 points beyond $(m - M) = 28.2$ (omitting NGC 524 with only a lower limit to its distance) leads to a Hubble line with large scatter ($\sigma_{(m-M)} = 0.43 \text{ mag}$) and very steep slope. The non-linearity is so pronounced that H_0 increases from 62.9 to 82.1 as one goes from $(m - M) = 29.0$ to 31.5! The reason may be that the brightness of the brightest planetary nebulae depends on galaxy size (Bottinelli et al. 1991; Tammann 1993). Whatever the reason, the luminosity function of planetary nebulae is not a useful distance indicator.

3. THE TEST FOR LINEARITY OF THE LOCAL EXPANSION FIELD

As said at the end of § 1.2, the test for linearity – the test if H_0 is or is not a function of distance in the world map – is model-dependent because it depends on transforming the world picture into the world map. This can only be done by using the $R(t)$ scale factor which depends on the model, and by taking account of the streaming motions where they exist.

The problem and its evident degeneracy is illustrated by the deviation of the slopes in Table 3 from 0.200 which is the value if the world *map* describes a homogeneous and isotropic universe in the mean. The naive interpretation of the mean slope of 0.193 ± 0.002 would be that the Hubble constant *decreases* outward such that if $H_0 = 62.3$ locally at say $v = 1000 \text{ km s}^{-1}$, then the value at $10,000 \text{ km s}^{-1}$ would be 58.0.

However, such a conclusion is incorrect. It ignores the transformation of the world picture into the world map via a Mattig-like equation where a second parameter is required in the theoretical, model dependent equation for the Hubble diagram.

We test first in § 3.1 for linearity in case of a fixed value of q_0 and then investigate in § 3.2 the range of q_0 for which linearity cannot be excluded using only the local data with $z < 0.1$.

3.1. The Test for Linearity Using a World Model with $\Omega_M = 0.3, \Omega_\Lambda = 0.7$

In a first step of the linearity test we adopt the values of the “concordance model” of $\Omega_M = 0.3, \Omega_\Lambda = 0.7$, which corresponds to $q_0 = -0.55$.

The velocity residuals $\Delta \log v$ of the objects in Figure 2 from the Hubble line calculated with equation (1) are plotted against the adopted distance moduli in Figure 6a. The scatter of the residuals increases towards smaller distances due to the relatively larger contribution of peculiar motions to the recession velocities. The distribution of the points is as flat as can be expected, giving a slope of 0.000 ± 0.001 . This implies that the value of H_0 remains constant to within $\pm 2.3\%$ over a modulus interval of $\Delta(m - M) = 10$, corresponding to a distance factor of 100.

In order to test for *local* distance-dependent variations of H_0 the data of Figure 6a are averaged per bins of width $\Delta(m - M) = 0.5$ mag and shown in Figure 6b. The 21 averaged residuals between $(m - M) = 28.0$ and 38.0 are about normally distributed and have an average rms deviation of $\sigma_{\Delta \log v} = 0.012$ from the adopted horizontal line, which restricts the local variations of H_0 to 2.8% on average. Individual intervals with 10 or less objects deviate by up to 7% . Shifting the boundaries of the bins does not change this result.

Earlier suggestions of H_0 to decrease gradually by 5% out to $18,000 \text{ km s}^{-1}$ (Tammann 1999) cannot be maintained in the light of the present, much increased data, which also deny the so-called “Hubble Bubble”. This feature was proposed as a drop of H_0 by $6.5 \pm 2.0\%$ beyond a distance of $\sim 7200 \text{ km s}^{-1}$ (corresponding to $(m - M) = 35.3$ in the adopted distance scale) by Zehavi et al. (1998) and Jha et al. (2007). This drop has been taken as support for a local overdensity and for a dark-energy-free cosmology (Wiltshire 2008). Yet Giovanelli et al. (1999), Conley et al. (2007), and Hicken et al. (2009) have questioned the result as we do here. Indeed comparing the bin in Figure 6b just preceding the break with the one following the break – either bin containing more than 30 objects – shows the more distant bin to lie *higher* by $\delta(\Delta \log v) = 0.005 \pm 0.008$ or H_0 to be *larger* by $1.3 \pm 1.7\%$. This rejects the Hubble Bubble at the level of 4 sigma. – It is also noted that the five intervals within $32.5 < (m - M) < 35.0$ and the five intervals within $35.5 < (m - M) < 38.0$, embracing the break point and comprising a total of more than 100 objects each, give an increase of H_0 with distance of $0.5 \pm 1.2\%$ instead of the putative decrease of $\sim 6.5\%$. This rejects a persistent decrease of H_0 at an even higher level of significance.

3.2. The Model Dependence of the Linearity Test

It is interesting to ask for the sensitivity of the test for linearity for a range of world models.

3.2.1. The linearity test for different values of Ω_M, Ω_Λ

We first consider two *flat* Λ CDM models with rather extreme values of $(\Omega_M, \Omega_\Lambda) = (0.6, 0.4)$ and $(0.1, 0.9)$ corresponding to $q_0 = -0.10$ and -0.85 , respectively. The differences between the moduli $(m-M)_{\text{model}}$ for the two trial models from equation (1) and the moduli for the standard model under § 3.1 are listed in Table 4, Columns (3) & (4) for various values of z . The differences are shown as smooth curves in Figure 7, where the differences $\Delta(m-M)$ are plotted against $\log z$. Also shown are the mean values of $\Delta(m-M) = (m-M)_{\text{obs}} - (m-M)_{\text{standard model}}$ of all objects in Figure 6 averaged over intervals of $\Delta \log z = 0.3$ and plotted in steps of $\Delta \log z = 0.1$. The conclusion is that the averaged data points at larger distances fit reasonably within the boundaries of the two trial models. This means that linearity holds for all flat models with parameters between the two trial models. The weak restriction on the parameter space is no surprise in view of the short leverage in z of the data used.

3.2.2. The linearity test for different values of q_0

We now relax the condition of a flat model and specify the trial models only by q_0 . For this purpose we recall the derivation of the theoretical Hubble diagram of $\log z$ vs. apparent magnitude using a standard candle in various homogeneous, isotropic universes.

Robertson’s (1938) equation that relates the apparent luminosity, l , with the metric distance at the present instant of cosmic time is

$$l = L[(4\pi R_0 r)^{-2}(1+z)^{-2}] \quad (2)$$

where L is the absolute luminosity and $R_0 r$ is the metric distance where r is the constant (for all time) dimensionless metric distance, and R_0 is given by the Mattig solution (for $\Lambda = 0$) as

$$R_0 r = \frac{c}{H_0 q_0^2 (1+z)} [z q_0 + (q_0 - 1) \{-1 + (2q_0 z + 1)^{1/2}\}]. \quad (3)$$

Combining equations (2) and (3) gives the equation for the theoretical Hubble diagram to be

$$(m-M) = 5 \log q_0^{-2} [z q_0 + (q_0^{-1}) \{-1 + (2q_0 + 1)^{1/2}\}] + C, \quad (4)$$

where C contains the Hubble constant and the intrinsic mean absolute magnitude of the distance indicator.

The series expansion of equation (4), is

$$(m-M) = 5 \log z + 1.086(1 - q_0)z + 1/6(2 - q_0 - 3q_0^2)z^2 + O(z^3) + C. \quad (5)$$

For small values of z equation (5) is also valid if $\Lambda \neq 0$. The effect of the third term is ≤ 0.003 for $q_0 > -1$ and $z < 0.1$.

The values of $(m-M)$ are calculated from equation (5) for four trial values of $q_0 = 0.00, -0.20, -0.80$, and -1.00 and for various values of z . Subtracting from these values the modulus $(m-M)$ resulting from $q_0 = -0.55$ and the corresponding values of z , one obtains the values $\Delta(m-M)_{\text{model}}$ listed in Table 4 (Col. 5-8) and shown in Figure 7 as smooth dashed lines. As in § 3.2.1 the more distant data points lie within the boundaries for $q_0 = 0.00$ and -1.00 . The conclusion is that q_0 is probably negative irrespective of the value of Λ .

3.3. The Linearity of the Expansion at Large Scales

If linear expansion – albeit for a considerable range of parameters – was found in the foregoing from a sample arbitrarily cut at $z < 0.1$ ($30,000 \text{ km s}^{-1}$), there is sufficient overlap with other SNIa samples extending to higher redshifts to carry the linearity test to $z > 1$ (§ 1.3).

The main conclusion of § 3 is that the cosmic expansion is linear on all scales. This holds surprisingly, if corrections are applied for the local Virgocentric flow and for the bulk motion of the Local Supercluster toward the warm pole of the CMB (see § 4), down to distances of 300 km s^{-1} ($\sim 5 \text{ Mpc}$).

4. THE SIZE OF THE VOLUME CO-MOVING TOWARDS THE CMB APEX

As evidenced by the dipole of the CMB radiation the LG partakes of a bulk motion in addition to the Virgocentric vector. The dipole, first received with disbelief, was discovered by Henry (1971), Corey & Wilkinson (1976), and Smoot et al. (1977). After attempts to explain the dipole as a primordial effect (Gunn 1988; Paczynski & Piran 1990) it soon became clear that it could be caused only by a local motion which, seen from the Sun, amounts to $369 \pm 2 \text{ km s}^{-1}$ towards the observed apex A_{obs} at $l = 263.86 \pm 0.04$, $b = 48.24 \pm 0.10$ (Bennett et al. 1996; Hinshaw et al. 2007) or, if translated to the barycenter of the LG following Yahil

et al. (1977), to $v_{\text{LG}} = 626 \pm 30 \text{ km s}^{-1}$ towards $l = 276 \pm 2$, $b = 30 \pm 2$. Subtracting the Virgocentric infall vector from v_{LG} one obtains a velocity of the LG of $v_{\text{CMB}} = 495 \pm 25 \text{ km s}^{-1}$ towards the corrected CMB apex A_{corr} at $l = 275 \pm 2$, $b = 12 \pm 4$ (cf. also Sandage & Tammann 1984). It was clear from the beginning that a velocity of such size must comprise a very large volume including the Virgo cluster and extending to at least 1500 km s^{-1} because otherwise two galaxies at roughly equal distances in the apex and antapex direction would differ in redshift by 990 km s^{-1} ! The conclusion is that the whole Local Supercluster moves more or less coherently towards the CMB apex.

Figure 8 shows the aspect of the Hubble diagram if the Galaxy were the only object moving towards the CMB pole with a velocity of 495 km s^{-1} . In that case all other nearby galaxies, being at rest in co-moving coordinates with respect to the CMB, would exhibit large peculiar motions as seen from the LG and fill the Hubble diagram within the wide curved envelopes as shown in the Figure. The assumption, besides being unphysical, is clearly contradicted by the concentration of the observed galaxies (repeated from Fig. 2) towards the center line of the diagram. Most galaxies within say 1000 km s^{-1} must share the CMB motion of the Galaxy. Beyond this point the diagram loses its diagnostic power because the vector of 495 km s^{-1} is drowned in the recession velocities of more distant galaxies and in the natural scatter.

The convergence radius of the Local Supercluster, i.e. the distance where field galaxies merge into the inertial frame of the CMB has been determined by several authors, some of which are compiled in Table 5. The size and direction of the bulk motion from the different authors are not listed in Table 5, because some authors postulate additional velocity vectors on larger scales to explain the full CMB dipole motion. One of the reasons – besides systematic distance errors which always lead to large-scale motions – may be that they have not allowed for Virgocentric infall vectors and that they have compared their results with the CMB apex A_{obs} instead of A_{corr} (i.e. after correction of the local Virgocentric infall vector of 220 km s^{-1}).

A direct determination of the size of the Local Supercluster and its bulk motion is obtained when one plots the velocity residuals from the Hubble line $\Delta v_{220} = v_{220} - v_{\text{model}}$ against the angle α from the apex A_{corr} . Galaxies from Figure 2 are divided into two bins, $500 < v_{220} < 3500$ and $3500 < v_{220} < 7000 \text{ km s}^{-1}$ and their apex diagrams are shown in Figure 9a,b. The result is striking. The distribution of the nearer sample is flat and the more distant sample reflects a local peculiar velocity of $448 \pm 73 \text{ km s}^{-1}$ in satisfactory agreement with the corrected CMB dipole motion of $495 \pm 25 \text{ km s}^{-1}$. Clearly the majority of galaxies within $\sim 3500 \text{ km s}^{-1}$ share the coherent bulk motion of the Local Supercluster, whereas the galaxies beyond this limit are in rest with respect to the inertial frame of the CMB.

The scatter in Figure 9b is significantly larger than in Figure 9a. This is because the distance errors of $\gtrsim 6\%$ predict velocities with errors increasing with distances such as to overwhelm eventually the signal from streaming velocities. For this reason the apex diagrams should not be carried much beyond 7000 km s^{-1} .

Aiming for a still better determination of the convergence length, the objects of Figure 9 in the range $2400 < v_{220} < 4800 \text{ km s}^{-1}$ have been re-binned in 1000 km s^{-1} intervals and are plotted in steps of 200 km s^{-1} in Figure 10. The nearer samples in panel a) and b) show already a marginal slope suggesting that the Local Supercluster begins to peter out at even smaller velocities (distances) than 3500 km s^{-1} . Panel c) centered at 3300 km s^{-1} support that conclusion at the 1.6σ level, while panel d) centered at 3500 km s^{-1} shows a highly significant apex motion. Finally the more distant panels e)–h) are fully consistent with the expected asymptotic apex motion of $495 \pm 25 \text{ km s}^{-1}$.

The conclusion is that the convergence distance is reached close to 3500 km s^{-1} . The exact convergence distance depends presumably on direction, but for a corresponding test the large, yet still restricted sample is not adequate.

For visualization the 90 objects in Figure 9b (i.e. with $3500 < v_{220} < 7000 \text{ km s}^{-1}$) are plotted in an Aitoff projection (Fig. 11). The association of the objects with positive and negative velocity residuals with their respective apices is striking. The eccentric position of the apices within their associated objects is due to the paucity of objects in the zone of avoidance. The lopsided distribution of the available objects about the apices is also the reason why we have not independently solved for the direction of the apex, but have taken the CMB dipole direction as given.

The flow pattern of the 144 sample objects with $500 < v_{220} < 10,000 \text{ km s}^{-1}$ and $|\beta| < 45^\circ$ is shown in Figure 12. Their distances and velocity residuals $\Delta v_{220} = v_{220} - v_{\text{model}}$ are projected on the “apex plane” which is tilted against the Galactic plane by 12° and rotated such that the CMB apex A_{corr} has the new coordinates $\lambda = 270^\circ$, $\beta = 0^\circ$. The objects within 3500 km s^{-1} have small velocity residuals, whereas the more distant objects have larger velocity residuals on average. The distribution of the available objects beyond 3500 km s^{-1} , although not forming a complete nor objectively selected sample, is far from random. Of the 18 objects in the 45° sector about the apex direction 12 have negative and 6 have positive velocity residuals. The chance probability for this distribution is 12%. Of the 29 objects in the corresponding sector about the antapex direction 25 have positive and 4 have negative velocity residuals. In this case the chance probability is only $P = 0.01\%$. The bulk motion of the Local Supercluster is hence reflected in Figure 12 at a high level of significance. Consistent with this is the nearly random distribution of the velocity residuals in the two perpendicular sectors about $\lambda = 0^\circ$ and $\lambda = 180^\circ$.

5. RESULTS AND CONCLUSIONS

Exceptionally accurate relative distances are compiled from eight sources in § 2.1. They are based on SN Ia magnitudes and on mean 21cm line widths and the Fundamental Plane in case of clusters. They are normalized to an arbitrary value of H_0 of 62.3 without loss of generality. Accurate TRGB and Cepheid distances were added in § 2.2. The final Hubble diagram with 480 objects extends from 300 to 30,000 km s⁻¹ and has a scatter of only 0.15 mag (8% in linear distance) beyond 3000 km s⁻¹; the increase of the scatter at shorter distances, due to peculiar motions, is compensated by large-number statistics.

The expansion of space is as linear as can be measured after allowance is made for a Virgocentric flow model and for the CMB motion of the Local Supercluster. Over the range of 300 to 30,000 km s⁻¹ the value of H_0 does not change systematically by more than $\pm 2.3\%$. At poorly populated distances H_0 may locally vary by 7%. But the so-called Hubble Bubble suggesting a sudden decrease of H_0 by 6.5% – be it a local dip or a persistent feature beyond – at the particularly well occupied distance around 7200 km s⁻¹ is excluded by 4σ or more.

The question at which distance the cosmic value of H_0 can be found is answered by Figure 6: beyond $(m - M) = 28.0$ (~ 4 Mpc) and out to at least 20,000 km s⁻¹ any systematic deviation from linear expansion is limited to a few percent. At 20,000 km s⁻¹ the expansion field is well tied to the equally linear large-scale expansion field (e.g. Kessler et al. 2009). The cosmic value of H_0 can therefore be found quite locally if sufficient calibrators are available to compensate the locally important peculiar velocities. The available 78 TRGB distances outside $(m - M) = 28.0$ yield a well determined value of $H_0 = 62.9 \pm 1.6$ (statistical error) in good agreement with local Cepheids and SNe Ia (Tammann et al. 2008a). Allowing for a 0.10 mag error of the TRGB zero point, based on RR Lyr stars and other distance determinations, and for a generous variation of H_0 with distance of 0.10 mag gives a compounded error of H_0 of ± 4.7 (8%), including the statistical error. The discrepancy with values of $H_0 > 70$ (e.g. Riess et al. 2009) is not a subject of the present paper.

The Local Supercluster emerges as a comoving entity of radius 3500 km s⁻¹, corresponding to a diameter of ~ 110 Mpc, with the Virgo cluster at its center and several additional clusters (UMa, Fornax, Eridanus) and a large number of groups which must induce a network of small peculiar motions not considered in this paper (see Klypin et al. 2003, for a map). Inside the Supercluster the expansion is decelerated about inversely to the distance from the Virgo cluster. The galaxies of the Supercluster are concentrated toward the supergalactic plane (de Vaucouleurs 1956) which extends to at least 4500 km s⁻¹ (Lahav et al. 2000). It is to be noted that the CMB apex A_{corr} lies at supergalactic latitude -39° , which shows that objects near to the plane (like the Great Attractor and the Shapley Concentration) can contribute only a fraction of the acceleration of the Local Supercluster.

The Supercluster’s reflex motion with respect to galaxies beyond 3500 km s^{-1} amounts to $448 \pm 73 \text{ km s}^{-1}$ in good agreement with the velocity of $495 \pm 25 \text{ km s}^{-1}$ toward an apex in the zone of avoidance ($l = 275 \pm 2$, $b = 12 \pm 4$) as inferred from the CMB dipole after correction for the local Virgocentric infall vector. The infall vector at the position of the LG amounts to $220 \pm 30 \text{ km s}^{-1}$ and diminishes for larger Virgocentric velocities according to the mass profile of the Supercluster. The question as to the exact shape of the Local Supercluster is very complex as evidenced for instance by the near component of the Centaurus cluster (Lucey et al. 1991; Stein et al. 1997), and the Pegasus and Hydra clusters all three of which lie near to its outer boundary.

The Local Supercluster is the largest volume to our knowledge for which an unambiguous peculiar motion has been found. Claims for coherent streaming motions over still larger scales are either disproven or remain very doubtful in view of possible systematic errors of the applied distance indicators with large intrinsic scatter. In any case any large-scale streaming motion of which the Local Supercluster could partake is limited by the agreement between the absolute CMB dipole motion of $495 \pm 25 \text{ km s}^{-1}$ and the observed bulk motion of $448 \pm 73 \text{ km s}^{-1}$ with respect to galaxies beyond 3500 km s^{-1} . The question as to the relation between volume size and corresponding peculiar velocity is decisive for the theory of structure evolution which predicts decreasing peculiar velocities with increasing structure size. Λ CDM models with $\Omega_M = 0.3$, $\Omega_\Lambda = 0.7$ predict quite generally that a bulk motion of $\lesssim 500 \text{ km s}^{-1}$ lies in the upper, yet permissible range for a volume of radius 3500 km s^{-1} (Dekel 2000, Fig. 1; Colless et al. 2001, Fig. 14).

The bulk motions of galaxy concentrations outside the Local Supercluster are still difficult to determine in view of the remaining distance errors. The one-dimensional bulk velocities in the inertial frame of the CMB of the 28 (super-) clusters and groups with $3500 < v_{\text{CMB}} < 10,000 \text{ km s}^{-1}$ contained in Table 1 are compiled in Table 6 (in order of RA). Columns (1)–(3) give the name of the cluster, its adopted distance modulus μ^0 from SNe Ia, $D_n - \sigma$ and/or fundamental plane distances, and the number of distance determinations, respectively. The observed mean cluster velocity, expressed as v_{CMB} is in column (4). The expected velocity v_{model} in column (5) is calculated for $H_0 = 62.3$, $\Omega_M = 0.3$, and $\Omega_\Lambda = 0.7$ as throughout in this paper. The bulk velocity $v_{\text{CMB}} - v_{\text{model}}$ and its error follow in column (6). The 1σ error is estimated by assuming here a distance error of 7.5% for one distance determination and of 5% for two or three distance determinations. The average (absolute) bulk velocity of the 28 aggregates is 353 km s^{-1} . However the signal of 353 km s^{-1} is smaller than the average error of 387 km s^{-1} , questioning whether any of the bulk velocities are significant. If one considers instead only the 11 clusters and groups with $3500 < v_{\text{CMB}} \leq 5000 \text{ km s}^{-1}$, for which the distance errors are less effective, one obtains an average bulk motion of $175 \pm 250 \text{ km s}^{-1}$, or $303 \pm 432 \text{ km s}^{-1}$ in three dimensions. In the

sample of 11 only the Hydra cluster has a bulk radial velocity with a significance of 1.9σ , i.e. $-349 \pm 199 \text{ km s}^{-1}$ toward the Local Supercluster. Peculiar velocities of large aggregates of some hundred km s^{-1} appear to be compatible with the data. The one-dimensional bulk velocity of the Local Supercluster of $480 : \sqrt{3} = 280 \text{ km s}^{-1}$, as seen from a random external observer, is therefore not exceptional.

It is unphysical to seek for a single attractor accelerating the Local Supercluster as has been proposed in the case of the Great Attractor (see § 2.3.1) or the Shapley Concentration (Mathewson et al. 1992; Saunders et al. 2000; Kocevski & Ebeling 2006; Basilakos & Plionis 2006), because they are 53 and 34 degrees away from the apex direction A_{corr} . It is clear that instead the acceleration must be caused by the integrated force exerted by all surrounding mass concentrations and voids. A lower distance limit of the dominant accelerators is set by the radius of the Local Supercluster of $\sim 3500 \text{ km s}^{-1}$. A direct determination of the convergence depth is afforded by integrating the light of all-sky samples of galaxies up to the point where the light dipole – which is the same as the dipole of the gravitational pull if the mass-to-light ratio is assumed to be constant – agrees with the CMB dipole (see Yahil et al. 1980a; Davis & Huchra 1982; Lahav 1987; Lynden-Bell et al. 1989; Strauss et al. 1992; Maller et al. 2003). Particularly suited for this purpose is the relatively absorption-free $2 \mu\text{m}$ all-sky 2MASS Redshift Survey from which Erdoğan et al. (2006a) have derived – by excluding a few nearby galaxies and integrating out to 3000 km s^{-1} – an apex at $l = 269 \pm 9$, $b = 37 \pm 9$. This agrees well with the CMB apex at $l = 276 \pm 2$, $b = 30 \pm 2$ as seen from the Local Group (see § 4).³ The agreement is only marginally improved if the integration is carried out to 5000 km s^{-1} . The conclusion is that most of the acceleration of the Local Supercluster comes from a distance of $\sim 4000 \pm 1000 \text{ km s}^{-1}$. A map of the dominant overdensities (in $2 \mu\text{m}$) and voids within a shell centered at 4000 km s^{-1} is given by Erdoğan et al. (2006b, their Fig. 4). The structures seen in this shell are probably the main players accelerating the Local Supercluster.

A.S. thanks the Observatories of the Carnegie Institution for post-retirement facilities. G.A.T. thanks Prof. Norbert Straumann for stimulating discussions. The authors thank the Referee for helpful comments.

³In this case the dipole of the integrated light must be compared with the CMB apex as seen from the Local Group and not with the apex A_{corr} , i.e. corrected for Virgocentric infall, because the integration starts at small velocities and includes the Virgo cluster.

REFERENCES

- Aaronson, M., et al. 1982, ApJS, 50, 241
- Aaronson, M., Bothun, G., Mould, J., Schommer, R. A., & Cornell, M. E. 1986, ApJ, 302, 536
- Basilakos, S., & Plionis, M. 2006, MNRAS, 373, 1112
- Bennett, C. L., et al. 1996, ApJ, 464, L1
- Bondi, H. 1960, Cosmology (Cambridge: Cambridge Univ. Press)
- Bottinelli, L., Gouguenheim, L., Fouqué, P., Paturel, G., & Teerikorpi, P. 1987, A&A, 181, 1
- Bottinelli, L., Gouguenheim, L., Paturel, G., & Teerikorpi, P. 1986, A&A, 156, 157
- Bottinelli, L., Gouguenheim, L., Paturel, G., & Teerikorpi, P. 1988, ApJ, 328, 4
- Bottinelli, L., Gouguenheim, L., Paturel, G., & Teerikorpi, P. 1991, A&A, 252, 550
- Bowers, R., & Deeming, T. 1984, Astrophysics II: Interstellar Matter and Galaxies (Boston: Jones & Bartlett)
- Burstein, D. 1990, Rep. Prog. Phys., 53, 421
- Carpenter, E. F. 1938, ApJ, 88, 344
- Carroll, S. M., Press, W. H., & Turner, E. L. 1992, ARA&A, 30, 499
- Carroll, B. W., & Ostlie, D. A. 1996, An Introduction to Modern Astrophysics (New York: Addison)
- Charlier, C. V. L. 1908, Ark. Mat. Astron. Fys. 4, 1
- Charlier, C. V. L. 1922, Ark. Mat. Astron. Fys. 16, 1; Medd. Lund. Obs. No. 98
- Ciardullo, R., Feldmeier, J. J., Jacoby, G. H., Kuzio de Naray, R., Laychak, M. B., & Durrell, P. R. 2002, ApJ, 577, 31
- Colless, M., Saglia, R. P., Burstein, D., Davies, R. L., McMahan, R. K., & Wegner, G. 2001, MNRAS, 321, 277
- Conley, A., Carlberg, R. G., Guy, J., Howell, D. A., Jha, S., Riess, A. G., & Sullivan, M. 2007, ApJ, 664, 13

- Corey, B. E., & Wilkinson, D. T. 1976, *BAAS*, 8, 351
- Davis, M., & Huchra, J. 1976, *ApJ*, 254, 437
- Dale, D. A., Giovanelli, R., Haynes, M. P., Campusano, L. E., Hardy, E., & Borgani, S. 2000, *ApJ*, 510, L11
- de Freitas Pacheco, J. A. 1986, *Rev. Mex. AA*, 12, 74
- Dekel, A. 2000, in *ASP Conf. Ser. 201, Cosmic Flows Workshop*, ed. S. Courteau & J. Willick (San Francisco: ASP), 420
- de Vaucouleurs, G. 1956, *Vistas in Astronomy*, 2, 1584
- de Vaucouleurs, G. 1970, *Science*, 167, 1203
- de Vaucouleurs, G. 1971, *PASP*, 83, 113
- Dressler, A. 1984, *ApJ*, 281, 512
- Dressler, A. 1987, *Sci. Am.*, 257, 46
- Erdoğdu, P., et al. 2006a, *MNRAS*, 368, 1515
- Erdoğdu, P., et al. 2006b, *MNRAS*, 373, 45
- Faber, S. M., & Burstein, D. 1988, in *Large-scale motions in the universe* (Princeton: Princeton Univ. Press), 115
- Faber, S. M., Burstein, D., Davies, R. L., Dressler, A., Lynden-Bell, D., Terlevich, R., & Wegner, G. 1988, in *IAU Symp. 130, Large Scale Structures of the Universe*, ed. J. Audouze, M.-C. Pelletan, & S. Szalay (Dordrecht: Kluwer), 169
- Faber, S. M., Wegner, G., Burstein, D., Davies, R. L., Dressler, A., Lynden-Bell, D., & Terlevich, R. J. 1989, *ApJS*, 69, 763
- Fall, S. M., & Jones, B. J. T. 1976, *Nature*, 262, 457
- Federspiel, M., Sandage, A., & Tammann, G. A. 1994, *ApJ*, 430, 29
- Feldmeier, J. J., Jacoby, G. H., & Philips, M. M. 2007, *ApJ*, 657, 76
- Freedman, W. L., et al. 2009, *ApJ*, 704, 1036
- Giovanelli, R., Haynes, M. P., Salzer, J. J., Wegner, G., da Costa, L. N., & Freudling, W. 1998, *AJ*, 116, 2632

- Giovanelli, R., Dale, D. A., Haynes, M. P., Hardy, E., & Campusano, L. E. 1999, *ApJ*, 525, 25
- Giraud, E. 1990, *A&A*, 231, 1
- Gunn, J. E. 1988, in *ASP Conf. Ser. 4, The Extragalactic Distance Scale*, ed. S. van den Bergh & C. J. Pritchett (San Francisco: ASP), 344
- Gunn, J. E., & Oke, J. B. 1975, *ApJ*, 195, 255
- Guy, J., Astier, P., Nobili, S., Regnault, N., & Pain, R. 2005, *A&A*, 443, 781
- Guy, J., et al. 2007, *A&A*, 466, 11
- Haggerty, M. J. 1970, *Physica*, 50, 391
- Haggerty, M. J. 1971, *MNRAS*, 155, 495
- Harrison, E. R. 1981, 2000, *Cosmology: The Science of the Universe* (Cambridge: Cambridge Univ. Press)
- Harrison, E. R. 1993, *ApJ*, 403, 28
- Heckmann, O. 1942, *Theorien der Kosmologie* (Berlin: Springer)
- Henry, P. S. 1971, *Nature*, 231, 516
- Herrmann, K. A., Ciardullo, R., Feldmeier, J. J., & Vinciguerra, M. 2007, *ApJ*, 683, 630
- Hicken, M., Wood-Vasey, W. M., Blondin, S., Challis, P., Jha, S., Kelly, P. L., Rest, A., & Kirshner, R. P. 2009, *ApJ*, 700, 1097
- Hinshaw, G., et al. 2007, *ApJS*, 170, 288
- Hoffman, J. H., Olson, D. W., & Salpeter, E. E. 1980, *ApJ*, 242, 861
- Hoffman, Y., Eldar, A., Zaroubi, S., & Dekel, A. 2001, preprint (astro-ph/0102190)
- Hubble, E. 1929, *Proc. Nat. Acad. Sci.*, 15, 168
- Hubble, E., & Humason, M. L. 1931, *ApJ*, 74, 43
- Humason, M. L., Mayall, N. U., & Sandage, A. R. 1956, *AJ*, 61, 97
- Jha, S., Riess, A. G., & Kirshner, R. P. 2007, *ApJ*, 659, 122

- Jerjen, H., & Tammann, G. A. 1993, *A&A*, 276, 1
- Jones, D. H., et al. 2004, *MNRAS*, 355, 747
- Jørgensen, I., Franx, M., & Kjaergaard, P. 1996, *MNRAS*, 280, 167
- Kessler, R., et al. 2009, *ApJS*, 185, 32
- Klypin, A., Hoffman, Y., Kravtsov, A. V., & Gottlöber, S. 2003, *ApJ*, 596, 19
- Kocevski, D. D., & Ebeling, H. 2006, *ApJ*, 645, 1043
- Komatsu, E., et al. 2009, *ApJS*, 180, 330
- Kraan-Korteweg, R. C. 1986, *A&AS*, 66, 255
- Lahav, O. 1987, *MNRAS*, 225, 213
- Lahav, O., Santiago, B. X., Webster, A. M., Strauss, M. A., Davis, M., Dressler, A., & Huchra, J. P. 2000, *MNRAS*, 312, 166
- Lemaître, G. 1927, *Ann. Soc. Sci. Bruxelles A.*, 47, 49
- Lemaître, G. 1931, *MNRAS*, 91, 483
- Lilje, P. B., Yahil, A., Jones, B. J. T. 1986, *ApJ*, 307, 91
- Lucey, J. R., Lahav, O., Lynden-Bell, D., Terlevich, R. J., & Melnick, J. 1991, in *ASP Conf. Ser. 15, Large-Scale Structures and Peculiar Motions in the Universe*, ed. D. W. Latham & L. N. da Costa (San Francisco: ASP), 31
- Lynden-Bell, D., Faber, S. M., Burstein, D., Davies, R. L., Dressler, A., Terlevich, R. J., & Wegner, G. 1988, *ApJ*, 326, 19
- Lynden-Bell, D., Lahav, O., & Burstein, D. 1989, *MNRAS*, 241, 325
- Maller, A. H., McIntosh, D. H., Katz, N., & Weinberg, M. D. 2003, *ApJ*, 598, 1
- Masters, K. L., Springob, C. M., Haynes, M. P., & Giovanelli, R. 2006, *ApJ*, 653, 861
- Masters, K. L. 2008, *ASP Conf. Ser. 395, Frontiers of Astrophysics: Celebration of NRAO 50th Anniversary Science Symposium*, ed. A. H. Bridle, J. J. Condon, & G. C. Hunt (San Francisco: ASP), 137
- Mathewson, D. S., Ford, V. L., & Buchhorn, M. 1992, *ApJS*, 81, 413

- Mattig, W. 1958, *Astron. Nachr.*, 284, 109
- Mattig, W. 1959, *Astron. Nachr.*, 285, 1
- McVittie, G. C. 1974, *QJRAS*, 15, 246
- Milne, A. E. 1935, *Relativity, Gravitation and World Structure* (Oxford: Clarendon)
- Narlikar, J. V. 1983, 1993, 2002, *An Introduction to Cosmology* (Cambridge: Cambridge Univ. Press), Three Editions
- Paczynski, B., & Piran, T. 1990, *ApJ*, 364, 341
- Peacock, J. A. 1999, *Cosmological Physics* (Cambridge: Cambridge Univ. Press)
- Peebles, P. J. E. 1976, *ApJ*, 205, 318
- Peebles, P. J. E. 1980, *The Large-Scale Structure of the Universe* (Princeton: Princeton Univ. Press)
- Peebles, P. J. E. 1993, *Principles of Physical Cosmology* (Princeton: Princeton Univ. Press)
- Reindl, B., Tammann, G. A., Sandage, A., & Saha, A. 2005, *ApJ*, 624, 532
- Riess, A. G., Press, W. H., & Kirshner, R. P. 1995, *ApJ*, 445, L91
- Riess, A. G., et al. 2009, *ApJ*, 699, 53
- Robertson, H. P. 1928, *Phil. Mag.*, 5, 835
- Robertson, H. P. 1929, *Proc. Nat. Acad. Sci.*, 15, 822
- Robertson, H. P. 1933, *Rev. Mod. Phys.*, 5, 62
- Robertson, H. P. 1938, *Z. Astrophys.*, 15, 69
- Robertson, H. P. 1955, *PASP*, 67, 82
- Robertson, H. P., & Noonan, T. W. 1968, *Relativity and Cosmology* (Philadelphia: Saunders)
- Sahni, V., & Starobinsky, A. 2000, *Int. J. Mod. Phys. D*, 9, 373
- Sandage, A. 1975, in *Galaxies and the Universe*, Vol. 9 of Stars and Stellar Systems, ed. A. Sandage, M. Sandage, & J. Kristian (Chicago: Chicago Univ. Press), Chapter 19

- Sandage, A. 1988, *ARA&A*, 26, 561
- Sandage, A. 1994, *ApJ*, 430, 1
- Sandage, A. 1995, in *The Deep Universe*, Saas-Fee Advance Lecture Course 23, (Berlin: Springer), Chapters 5 and 10
- Sandage, A. 1999, *ARA&A*, 37, 445
- Sandage, A., & Tammann, G. A. 1975, *ApJ*, 197, 265 (appendix on the bias proof against the Rubin-Ford effect)
- Sandage, A., & Tammann, G. A. 1984, in *Large-Scale Structure of the Universe*, Cosmology and Fundamental Physics, ed. G. Setti & L. Van Hove (Garching: ESO), 127
- Sandage, A., Tammann, G. A., & Hardy, E. 1972, *ApJ*, 172, 253
- Sandage, A., Tammann, G. A., Saha, A., Reindl, B., Macchetto, F. D., & Panagia, N. 2006, *ApJ*, 653, 843
- Saunders, W., et al. 2000, in *ASP Conf. Ser. 218*, Mapping the Hidden Universe: The Universe behind the Milky Way – The Universe in HI, ed. R. C. Kraan-Korteweg, P. A. Henning, & H. Andernach (San Francisco: ASP), 141
- Smith, R. J., et al. 2004, *AJ*, 128, 1558
- Smoot, G. F., Gorenstein, M. V., & Muller, R. A. 1977, *Phys. Rev. Lett.*, 39, 898
- Spergel, D.N., et al. 2007, *ApJS*, 170, 377
- Springob, C. M., Masters, K. L., Haynes, M. P., Giovanelli, R., & Marinoni, C. 2007, *ApJS*, 172, 599
- Springob, C. M., Masters, K. L., Haynes, M. P., Giovanelli, R., & Marinoni, C. 2007, *ApJS*, 182, 474
- Springob, C. M., et al. 2010, *BAAS*, 41, 551
- Stein, P., Jerjen, H., & Federspiel, M. 1997, *A&A*, 327, 952
- Strauss, M. A., Yahil, A., Davis, M., Huchra, J. P., & Fisher, K. 1992, *ApJ*, 397, 395
- Tammann, G. A. 1993, in *IAU Symp. 155*, Planetary nebulae, ed. R. Weinberger & A. Acker (Dordrecht: Kluwer), 515

- Tammann G. A. 1999, in *Recent Developments in Theoretical and Experimental General Relativity, Gravitation, and Relativistic Field Theories*, ed. T. Piran & R. Ruffini (Singapore: World Scientific), 243
- Tammann, G. A., & Sandage, A. 1985, *ApJ*, 294, 81
- Tammann, G. A., Sandage, A., & Reindl, B. 2008a, *ApJ*, 679, 52
- Tammann, G. A., Sandage, A., & Reindl, B. 2008b, *A&ARv*, 15, 289
- Teerikorpi, P. 1975a, *A&A*, 45, 117
- Teerikorpi, P. 1975b, *Observatory*, 95, 105
- Teerikorpi, P. 1984, *A&A*, 141, 407
- Teerikorpi, P. 1987, *A&A*, 173, 39
- Theureau, G., Hanski, M. O., Coudreau, N., Hallet, N., & Martin, J.-M. 2007, *A&A*, 465, 71
- Tonry, J. L., & Davis, M. 1981, *ApJ*, 246, 680
- Tonry, J. L., Dressler, A., Blakeslee, J. P., Ajhar, E. A., Fletcher, A. B., Luppino, G. A., Metzger, M. R., & Moore, C. B. 2001, *ApJ*, 546, 681
- Walker, A. G. 1936, *Proc. London Math. Soc.*, 42, 90
- Wang, X., Wang, L., Pain, R., Zhou, X., & Li, Z. 2006, *ApJ*, 645, 488
- Watkins, R., Feldman, H. A., Hudson, M. J. 2009, *MNRAS*, 392, 743
- Wertz, J. R. 1970, Ph.D. thesis, Univ. Texas at Austin, Pub. Dept. Astr. Ser II, Vol. 3 No. 4
- Wiltshire, D. L. 2008, *Int. J. Mod. Phys. D.*, 17, 641
- Wood-Vasey, W. M., et al. 2008, *ApJ*, 689, 377
- Yahil, A. 1985, in *The Virgo Cluster of Galaxies*, ed. O.-G. Richter & B. Binggeli (Garching: ESO), 359
- Yahil, A., Sandage, A., & Tammann, G. A. 1980a, *ApJ*, 242, 448
- Yahil, A., Sandage, A., & Tammann, G. A. 1980b, in *Physical Cosmology*, ed. E. Balian, J. Audouze, & D. N. Schramm (Amsterdam: North-Holland), 127

Yahil, A., Tammann, G. A., & Sandage, A. 1977, ApJ, 217, 903

Zehavi, I., Riess, A. G., Kirshner, R. P., & Dekel, A. 1998, ApJ, 503, 483

Zwicky, F. 1962, in IAU Symp. 15, Problems of Extragalactic Research, ed. G. C. McVittie (New York: Macmillan), 347

Table 1. ADOPTED MEAN DISTANCES OF 281 SNe Ia AND CLUSTERS

Galaxy (1)	SNe (2)	cluster (3)	GLON (4)	GLAT (5)	v_{hel} (6)	v_{220} (7)	v_{CMB} (8)	μ^0 (9)	Apex (10)	Δv_{220} (11)	Source (12)
UGC 14	2006sr		108.87	-38.36	7237	7352	7069	35.33	151	230	5
UGC 40	2003it		110.66	-34.33	7531	7664	7362	35.47	153	76	5
UGC 52	2002hw		104.56	-52.64	5257	5309	5103	34.66	138	53	5
Anon 0010-49	1992au		319.12	-65.88	18287	18061	18267	37.43	84	-173	1,3
UGC 139	1998dk		102.85	-62.16	3963	3981	3826	33.86	129	330	1,3
NGC 105	1997cw		113.09	-49.48	5290	5369	5140	34.09	139	1314	1,3
Anon 0036+11	1996bl		116.99	-51.30	10793	10830	10651	36.16	137	476	1,2,3
NGC 191A	2006ej		113.14	-71.65	6131	6079	6021	35.00	119	-54	5
A2806	...	A2806	306.16	-60.90	8304	8075	8310	35.47	77	487	6
MCG -02-02-86	2003ic	A0085	115.24	-72.03	16690	16616	16583	36.86	118	2455	5
NGC 232	2006et		93.67	-85.93	6647	6528	6570	35.04	106	283	5
MCG +06-02-17	2006mo		121.85	-26.53	11093	11245	10941	36.41	150	-339	5
2MASX J0056-01	2006gt		125.75	-64.47	13422	13382	13309	36.74	123	-43	4b
Anon 0056-01	2006nz		125.82	-64.07	11468	11431	11355	36.51	123	-682	5
UGC 607	1999ef		125.71	-50.08	11733	11764	11602	36.74	134	-1660	1,3
UGC 646	1998ef		125.88	-30.57	5319	5473	5176	34.37	146	867	1,3
NGC 382	2000dk	N383Gr	126.84	-30.35	5229	5380	5088	34.56	145	357	1,2,3
NGC 383 Gr	...	N383Gr	126.84	-30.34	5098	5250	4957	34.52	145	319	6
A2877	...	A2877	293.13	-70.88	7405	7194	7396	35.46	84	-359	6
Anon 0116+01	2005ir		136.24	-61.42	22886	22842	22782	38.12	122	-1840	4b,5
ESO 352-57	1992bo		261.87	-80.35	5549	5380	5518	34.87	92	-402	1,2,3
NGC 507 Gr	...	N507Gr	130.64	-29.13	4934	5089	4802	34.35	142	525	6
NGC 0523	2001en	N507Gr	130.91	-28.32	4758	4919	4627	34.27	142	518	5
A0194	...	A0194	142.06	-63.10	5396	5370	5302	34.60	119	256	6,7
MCG -01-04-44	1998dm		145.97	-67.40	1959	1940	...	33.21	115	-773	1,3
Anon	2005hj		142.55	-62.76	17388	17336	17294	37.35	119	-265	4b,5
2MASX J0127+19	2005hf	A0195	134.47	-42.95	12924	12980	12804	36.64	134	141	5
IC 126	1993ae		144.62	-63.23	5712	5682	5621	34.70	118	330	1,3
UGC 1087	1999dk		137.35	-47.47	4485	4548	4372	34.22	130	246	1,2,3
NGC 632	1998es		143.19	-55.18	3168	3204	...	33.29	123	390	1,2,3
UGC 1162	2001eh		132.24	-20.37	11103	11269	10976	36.18	143	821	5
Anon 0145-56	1992br		288.01	-59.43	26382	26119	26411	38.23	72	226	1,2,3
NGC 673	1996bo		144.46	-48.96	5182	5224	5084	34.24	125	883	1,2,3
UGC 1333	2006ob		153.30	-59.00	17759	17708	17680	37.33	116	261	5
A0262	...	A0262	136.59	-25.09	4887	5048	4770	34.44	138	293	6
MCG +00-06-03	2005hc		155.87	-58.84	13771	13719	13696	36.85	115	-380	4b,5
2MASX J0158+36	2006td		137.68	-24.60	4761	4919	4647	34.65	137	-313	5
NGC 0809	2006ef		169.46	-64.80	5361	5288	5306	34.87	107	-494	5
MCG +06-06-12	2002hu		141.44	-22.27	8994:	9132:	8891:	36.28	134	-1796:	2
Anon 0227+28	2005eu		147.48	-30.06	10463	10558	10373	35.89	128	1387	4a
UGC 1993	1999gp		143.25	-19.51	8018	8172	7922	35.57	133	234	1,2,3,4a
NGC 976	1999dq		152.84	-35.87	4295	4387	4218	33.79	123	851	1,2,3
IC 1844	1995ak		169.66	-48.98	6811	6785	6767	35.04	109	540	1,2,3
UGC 2320	2003iv		162.50	-40.73	10285	10293	10230	36.29	114	-684	5
CGCG 539-121	2005ls		145.75	-14.64	6331	6508	6245	34.82	130	856	5

Table 1—Continued

Galaxy (1)	SNe (2)	cluster (3)	GLON (4)	GLAT (5)	v_{hel} (6)	v_{220} (7)	v_{CMB} (8)	μ^0 (9)	Apex (10)	Δv_{220} (11)	Source (12)
UGC 2384	2006os	A0397	161.38	-37.47	9836	9864	9780	35.86	116	817	5
A0397	...	A0397	161.91	-37.24	9803	9830	9749	35.87	115	742	6
A0400	...	A0400	170.24	-44.93	7315	7299	7276	35.19	108	615	6
ESO 300-09	1992bc		245.70	-59.64	5996	5791	6036	35.03	75	-426	1,2,3
MCG -01-09-06	2005eq		187.64	-51.74	8687	8598	8677	35.78	97	-129	4a,b
NGC 1259	2008L	A0426	150.24	-13.62	5816	5988	5745	34.63	126	803	5
NGC 1275	2005mz	A0426	150.58	-13.26	5264	5435	5194	34.72	125	34	5
NGC 1316	1981D	Fornax	240.16	-56.69	1760	1371	...	31.23	74	...	1,3
NGC 1316	1980N	Fornax	240.16	-56.69	1760	1371	...	31.71	74	...	1,3
Anon 0329-37	1992bs		240.03	-55.34	18887	18659	18938	37.68	73	-1699	1,2,3
NGC 1380	1992A	Fornax	235.93	-54.06	1877	1371	...	31.82	74	-64	1,2,3
Anon 0336-18	1992bp		208.83	-51.09	23684	23525	23713	37.79	85	2160	1,2,3
Anon 0335-33	1990Y		232.64	-53.85	11702	11496	11753	36.38	75	68	1,3
UGC 2829	2006kf		178.55	-35.71	6386	6378	6378	35.12	102	-98	5
ESO 156-08	1992bk	A3158	265.05	-48.93	17598	17333	17675	37.27	61	343	1,2,3
NGC 1448	2001el		251.52	-51.39	1168	1015	...	31.73	66	-362	1,2,3
Grm13	...	Grm13	266.04	-43.47	929	754	...	31.74	56	-629	7
A0496	...	A0496	209.57	-36.48	9863	9736	9928	36.03	78	-31	6
UGC 3108	2006lf		159.92	-1.93	3959	4150	3930	34.21	115	-132	4a
NGC 1699	2001ep		203.60	-27.55	3901	3850	3971	33.95	79	46	5
Anon 0459-58	1992bh		267.85	-37.33	13491	13220	13602	36.88	50	-1069	1,2,3
UGC 3218	2006le		147.89	12.18	5226	5479	5176	35.03	122	-738	4a
NGC 1819	2005el		196.17	-19.40	4470	4466	4535	34.21	83	183	4a,b
A0539	...	A0539	195.70	-17.72	8514	8486	8580	35.95	83	-936	7
UGC 3329	1999ek		189.40	-8.23	5253	5304	5314	34.59	87	213	1,2,3,4a
PGC 17787	1993ac		149.72	17.21	14690	14923	14652	37.00	118	-149	1,2,3
CGCG 308-09	2006N		149.44	19.97	4280	4561	4245	34.36	117	-24	4a
A3381	...	A3381	240.29	-22.70	10763	10561	10907	36.32	48	-565	7
UGC 3432	1996bv		157.34	17.97	4998	5247	4984	34.44	111	491	1,2,3
2MASX J0627-35	1999ao		243.83	-20.02	16189	15974	16342	37.21	44	-570	5
CGCG 233-023	2002kf		165.59	18.25	5786	5999	5799	34.98	104	-79	5
ESO 427-06	2004S		240.79	-14.79	2806	2672	...	33.47	43	-383	2
NGC 2258	1997E		140.22	25.82	4059	4374	4007	34.26	122	-7	1,2,3
UGC 3576	1998ec		166.30	20.71	5966	6180	5984	35.16	102	-415	1,3
UGC 3634	2005na		201.40	8.61	7891	7923	8005	35.57	72	-16	4a,b
NGC 2320	2000B		166.36	22.79	5944	6169	5964	34.76	102	669	1,3
A0569	...	A0569	168.57	22.81	6026	6237	6053	35.03	100	20	6
UGC 3725	2007au	A0569	167.38	23.53	6171	6390	6195	34.98	101	312	5
NGC 2268	1982B		129.24	27.55	2222	2610	...	32.48	128	668	1
UGC 3770	2000fa		194.17	15.48	6378	6469	6477	35.23	78	-338	1,2,3
UGC 3787	2003ch		207.22	10.26	7495	7504	7626	35.97	66	-2002	5
UGC 3845	1997do		171.00	25.27	3034	3279	...	33.69	97	-99	1,2,3
Anon 0741-62	1992bg		274.61	-18.35	10793	10537	10947	36.28	30	-391	1,2,3
MCG +08-14-43	2007R		174.35	28.16	9258	9443	9307	36.12	93	-727	5
NGC 2441	1995E		141.99	30.26	3470	3804	3430	33.66	118	472	1,2,3

Table 1—Continued

Galaxy (1)	SNe (2)	cluster (3)	GLON (4)	GLAT (5)	v_{hel} (6)	v_{220} (7)	v_{CMB} (8)	μ^0 (9)	Apex (10)	Δv_{220} (11)	Source (12)
UGC 4133	2006qo		161.38	31.68	9130	9368	9145	35.80	103	561	5
UGC 4195	2000ce		149.10	32.00	4888	5180	4869	34.69	112	-148	1,2,3,4a
CGCG 207-42	2006te		178.98	32.08	9471	9648	9536	36.08	88	-341	5
A0634	...	A0634	159.40	33.64	7945	8192	7957	35.72	104	-303	6
UGC 4322	2002he		153.60	33.98	7364	7631	7360	35.51	108	-95	5
Cancer	...	Cancer	202.55	28.69	4497	4613	4623	34.49	69	-252	6
NGC 4414	1974G		174.54	83.18	716	788	...	31.47	79	-433	1,2
UGC 4414	2005mc		202.50	30.23	7561	7656	7687	35.69	69	-724	5
NGC 2595	1999aa	Cancer	202.73	30.31	4330	4452	4457	34.52	69	-479	1,2,3
UGC 4455	2007bd		226.07	21.52	9299	9277	9474	35.89	47	107	5
NGC 2623	1999gd		198.84	33.97	5549	5682	5666	34.90	72	-179	1,2,3
MCG +03-22-20	2004gs		207.96	31.32	7988	8065	8126	35.78	64	-662	4b
UGC 4614	2005ms		186.90	38.49	7556	7727	7644	35.60	81	-319	5
MCG -01-23-08	2002hd		234.77	23.16	10493	10449	10680	35.93	40	1112	5
CGCG 180-22	1999X		186.59	39.59	7546	7726	7634	35.49	81	70	1,3
MCG +08-17-43	2001G		168.32	42.31	5028	5292	5072	34.37	94	686	5
A0779	...	A0779	191.07	44.41	6742	6913	6840	35.52	77	-848	6
NGC 2935	1996Z		253.59	22.57	2271	2280	...	32.76	23	72	1,2,3
NGC 2930	2005M		206.89	46.22	6599	6733	6728	35.35	66	-454	4b
UGC 5129	2001fe		203.70	46.88	4059	4240	4182	34.17	68	35	5
NGC 2962	1995D		230.00	39.67	1966	2120	...	32.85	48	-180	1,2,3
NGC 2986	1999gh		255.04	23.72	2302	2300	...	32.94	22	-97	1,2,3
UGC 5234	2003W		217.68	45.93	6017	6132	6164	34.89	59	297	5
NGC 3021	1995al		192.18	50.84	1541	1841	...	32.71	76	-317	1,2,3
UGC 5378	2007S		234.37	43.38	4161	4246	4332	34.26	47	-135	5
UGC 5542	2001ie		150.36	47.78	9215	9490	9223	35.89	103	319	5
Anon 1003-35	1993ag		268.44	15.93	14700	14542	14898	37.03	7	-732	1,2,3
Anon 1009-26	1992J		263.55	23.54	13491	13375	13691	36.62	16	651	1,3
CGCG 266-31	2002bf		156.46	50.08	7254	7521	7278	35.60	98	-525	3
NGC 3147	1997bq		136.29	39.46	2820	3188	...	33.45	116	161	1,2,3
NGC 3190	2002bo		213.04	54.85	1271	1573	...	32.20	64	-135	1,2,3,4a
MCG +03-27-38	2004L		223.79	54.79	9686	9790	9829	36.08	58	-199	5
UGC 5691	1991S		214.07	57.42	16489	16610	16617	37.28	64	-455	1,3
AS636	...	Antlia	272.95	19.19	2608	2541	...	33.40	8	-418	6
Anon 1034-34	1993B		273.33	20.46	20686	20538	20881	37.75	9	-456	1,2,3
NGC 3294	1992G		184.62	-59.84	1586	1542	...	32.70	100	-606	3
A1060	...	Hydra	269.63	26.51	3777	3717	3973	34.23	15	-604	6,7
MCG +11-13-36	2006ar		142.76	46.62	6757	7054	6747	35.46	107	-499	5
Anon 1039+05	2006al	A1066	241.92	51.69	20341	20380	20505	37.72	48	-339	5
NGC 3327	2001N		211.35	60.29	6303	6471	6424	35.11	67	24	5
NGC 3332	2005ki		236.83	54.27	5758	5858	5914	34.96	52	-165	4b,5
AS639	...	AS639	280.54	10.91	6326	6171	6512	34.89	6	337	7
NGC 3368	1998bu		234.44	57.01	897	719	...	30.45	55	-45	1,2,3,4a
NGC 3370	1994ae		225.35	59.67	1279	1603	...	32.63	60	-477	1,2,3
UGC 6015	2006cf		165.96	60.09	12457	12690	12509	36.55	89	357	5

Table 1—Continued

Galaxy (1)	SNe (2)	cluster (3)	GLON (4)	GLAT (5)	v_{hel} (6)	v_{220} (7)	v_{CMB} (8)	μ^0 (9)	Apex (10)	Δv_{220} (11)	Source (12)
Anon 1101-06	1999aw		260.24	47.45	11992	11994	12168	36.59	38	-560	1,2,3
2MASX J1109+28	2006ak		203.15	67.48	11422	11595	11523	36.42	72	-41	5
NGC 3557 Gr	...	N3557Gr	281.58	21.09	3056	2990	...	33.51	11	-121	6
UGC 6211	2001ah		149.13	56.52	17315	17573	17334	37.21	98	1028	5
UGC 6332	2007bc		224.67	68.06	6227	6394	6346	35.13	65	-111	5
NGC 3627	1989B		241.96	64.42	727	431	...	30.35	57	-299	1,2,3
UGC 6363	2004bg		223.72	68.62	6306	6477	6423	35.10	65	60	5
NGC 3663	2006ax		271.83	45.23	5018	5041	5194	34.62	34	-120	4a,b
HOLM 254B	2004as		220.68	70.12	9300	9457	9412	36.13	67	-759	5
A1314	...	A1314	151.83	63.57	10043	10302	10076	36.05	93	446	6
ESO 439-18	2001ba		285.38	28.03	8861	8759	9041	35.97	19	-748	2,3,4a
EROS J1139-08	1999bp		274.68	50.04	23084	23075	23250	38.06	38	-970	5
A1367	...	A1367	234.80	73.03	6595	6765	6707	35.17	65	140	6
NGC 3873	2007ci	A1367	235.50	73.26	5434	5618	5546	34.78	66	68	5
NGC 3978	2003cq		134.85	55.31	9978	10270	9971	36.07	105	326	5
NGC 3982	1998aq		138.83	60.27	1109	1517	...	32.07	100	-92	1,2,3
NGC 3987	2001V		218.95	77.72	4502	4752	4596	34.18	72	527	1,2,3
NGC 4172	2006az		133.89	60.11	9274	9563	9276	35.91	102	309	5
UGC 7357	2006cp		243.90	81.31	6682	6873	6773	35.31	71	-185	4a
ESO 573-14	2000bh		293.74	40.34	6838	6812	6997	35.35	33	-375	2,3,4a
NGC 4321	2006X	Virgo	271.14	76.90	1571	1152	...	31.42	65	-42	4a
NGC 4419	1984A	Virgo	276.45	76.64	-261	1152	...	31.20	65	...	1
NGC 4493	1994M		291.69	63.04	6943	7034	7072	35.39	53	-284	1,2,3
NGC 4495	1994S		187.34	85.14	4550	4804	4619	34.47	78	-17	1,2,3
NGC 4496A	1960F	VirW	290.56	66.33	1730	1168	...	30.81	56	266	1
NGC 4501	1999cl	Virgo	282.33	76.51	2281	1152	...	31.33	65	...	4a
NGC 4520	2000bk		295.26	55.23	7628	7671	7767	35.70	46	-747	1,3,4a
NGC 4526	1994D	Virgo	290.16	70.14	448	1152	...	31.36	59	...	1,2,3
NGC 4536	1981B	VirW	292.95	64.73	1808	1407	...	31.26	54	...	1,2,3
NGC 4619	2006ac		136.98	81.80	6927	7174	6976	35.31	84	116	4a
Cen30	...	Cen30	300.97	22.15	3041	2991	...	33.44	27	-22	6
IC 3690	1992P		295.62	73.11	7615	7751	7720	35.71	63	-705	1,2,3
NGC 4639	1990N	Virgo	294.29	75.99	1018	1152	...	32.16	65	...	1,2,3
NGC 4675	1997Y		124.77	62.37	4757	5083	4753	34.60	102	-32	1,2,3
UGC 7934	2006S		131.43	81.95	9624	9856	9671	36.15	85	-453	5
2MASX J1246+12	2004gu		298.25	74.78	13748	13875	13848	36.78	64	209	4b
NGC 4680	1997bp		301.16	51.22	2492	2675	...	32.92	45	299	1,2,3
NGC 4679	2001cz		302.11	23.29	4643	4563	4794	34.37	29	-43	2,3,4a
NGC 4704	1998ab		124.87	75.20	8134	8407	8162	35.37	91	1154	1,2,3
NGC 4753	1983G		303.42	61.67	1239	1264	...	31.45	54	53	1
MGC -01-33-34	2006D		303.40	53.09	2556	2736	...	33.06	47	203	4a
2MASX J1259+28	2006cj		68.06	87.86	20241	20433	20297	37.96	80	-2583	5
A1656	...	Coma	58.08	87.96	6925	7152	6982	35.37	80	-100	6,7
IC 4042A	2006bz	Coma	55.57	87.78	8366	8583	8423	35.73	80	50	5
UGC 8162	2007F		118.24	66.40	7072	7367	7072	35.44	100	-118	5

Table 1—Continued

Galaxy (1)	SNe (2)	cluster (3)	GLON (4)	GLAT (5)	v_{hel} (6)	v_{220} (7)	v_{CMB} (8)	μ^0 (9)	Apex (10)	Δv_{220} (11)	Source (12)
2MASX J1305+28	2006cg		61.91	86.59	8413	8645	8466	35.26	81	1745	5
IC 4182	1937C		107.70	79.09	321	298	...	28.51	89	-15	1,2
MCG +06-29-43	2002G		96.96	82.19	10114	10347	10152	36.21	86	-243	5
ESO 508 Gr	...	E508 Gr	307.98	39.08	3196	3252	...	33.41	40	279	6
NGC 5018	2002dj		309.90	43.06	2816	2928	...	33.05	44	407	5
NGC 5061	1996X		310.25	35.66	2065	2157	...	32.45	40	242	1,2,3
PGC 46640	1994T		318.02	59.84	10390	10465	10493	36.20	58	-78	1,2,3
IC 4232	1991U		311.82	36.21	9426	9389	9554	35.74	41	818	1,3
ESO 508-67	1992ag		312.49	38.39	7795	7783	7921	35.33	43	661	1,2,3
IC 4239	2006cq		62.88	81.84	14491	14707	14528	36.98	85	-231	5
ESO 508-75	2007cg		312.72	37.57	9952	9919	10078	35.93	43	582	5
MCG -02-34-61	2007ca		316.95	46.69	4217	4264	4331	34.73	50	-1162	5
Anon 1331-33	1993O		312.42	28.92	15589	15502	15717	37.18	39	-824	1,2,3
ESO 383-32	2000ca		313.20	27.83	7080	7013	7206	35.31	39	-45	2,3,4a
NGC 5253	1972E		314.86	30.11	407	171	...	27.94	42	-69	1,2,3
NGC 5283	2005dv		115.81	48.76	3119	3489	...	33.93	117	-281	5
NGC 5308	1996bk		111.25	54.88	2041	2459	...	32.62	112	389	1,2,3
A3574	...	A3574	317.46	30.94	4797	4775	4913	34.43	44	41	6,7
NGC 5304	2005al	A3574	317.59	30.62	3718	3699	3833	34.39	44	-949	4b
MCG +08-25-47	1996C		99.62	65.04	8094	8384	8077	36.05	103	-1472	1,2,3
ESO 445-66	1993H		318.22	30.33	7257	7211	7371	35.33	44	89	1,2,3
AS753	...	AS753	319.63	26.55	4197	4167	4306	34.27	45	-234	7
NGC 5468	1999cp		334.87	52.70	2842	3010	...	33.46	63	-32	2,3,4a
NGC 5468	2002cr		334.87	52.70	2842	3006	...	33.58	63	-207	5
MCG +05-34-33	2002bz		36.89	69.23	11138	11357	11146	36.47	90	-542	5
IC 4423	2001ay		35.97	68.82	9067	9290	9075	36.09	90	-744	2,3
Anon 1433+03	2006bw		353.79	56.19	8994	9123	9036	35.87	74	35	5
UGC 9391	2003du		101.18	53.21	1914	2306	...	33.24	115	-445	2,3,4a
UGC 9612	2007O		77.66	59.25	10856	11144	10813	36.16	108	789	5
Anon	2005ag		7.85	55.50	23807	23945	23822	37.94	82	1128	4b
UGC 9640	2008af		20.11	58.62	10045	10236	10046	35.99	88	643	5
MCG -01-39-03	2005cf		354.81	39.85	1937	2136	...	32.38	75	282	4
UGC 10030	2002ck		6.55	39.30	8953	9068	8946	35.85	84	61	5
MCG +11-19-25	2000cf		99.88	42.17	10920	11241	10831	36.42	126	-395	1,2,3
MCG +03-41-03	2007ap		28.86	46.04	4742	4964	4701	34.77	98	-561	5
CGCG 108-13	2006bt		33.70	47.24	9640	9850	9593	36.03	100	83	5
IC 1151	1991M		30.36	45.90	2169	2436	...	33.64	99	-865	3
NGC 6038	1999cc		59.67	48.75	9392	9665	9320	36.01	112	-15	1,2,3
NGC 6063	1999ac		19.89	39.95	2848	3077	...	33.38	94	145	1,2,3
UGC 10244	2006cc		68.18	47.10	9752	10037	9670	36.31	117	-1038	5
ESO 584-07	2007ai		353.04	21.09	9492	9500	9499	36.00	75	-137	5
NGC 6104	2002de		57.37	45.91	8429	8702	8350	35.74	113	131	5
A2199	...	A2199	62.70	43.70	9039	9322	8949	35.76	117	673	6
UGC 10483	2001az		108.95	34.29	12200	12520	12100	36.58	132	21	5
PGC 59076	1994Q	A2199	64.39	39.68	8863	9148	8760	35.87	121	59	1,3

Table 1—Continued

Galaxy (1)	SNe (2)	cluster (3)	GLON (4)	GLAT (5)	v_{hel} (6)	v_{220} (7)	v_{CMB} (8)	μ^0 (9)	Apex (10)	Δv_{220} (11)	Source (12)
UGC 10704	2007ae		111.49	31.71	19303	19615	19201	37.33	134	2168	5
UGC 10738	2001cp		26.50	24.95	6716	6874	6634	35.29	104	-120	5
UGC 10743	2002er		28.67	25.83	2569	2796	...	33.15	106	157	1,2,3
MCG +03-44-03	1990O		37.65	28.37	9193	9389	9095	35.87	112	301	1,2,3
NGC 6365A	2003U		91.47	34.06	8496	8823	8377	35.64	134	630	5
NGC 6462	2005ao		90.99	31.49	11514	11828	11388	36.52	137	-340	4a
UGC 11064	2000cn		53.45	23.32	7043	7285	6908	35.41	127	-99	1,2,3
MCG +04-42-22	2001bf		52.16	21.97	4647	4911	4511	34.26	126	530	5
UGC 11149	1998dx		77.68	26.67	16256	16546	16113	37.02	138	1339	1,2,3
NGC 6627	1998V		43.94	13.34	5272	5480	5132	34.56	124	458	1,2,3
MCG +05-43-16	2007co		57.59	18.82	8083	8329	7933	35.57	132	391	5
NGC 6685	2006bq		68.85	19.09	6567	6851	6409	35.15	140	286	5
IC 4758	2001cn	PavoII	329.65	-24.05	4647	4475	4676	34.28	65	54	2,3,4a
AS805	...	PavoII	332.25	-23.59	4167	4002	4189	34.28	67	-419	6
2MASX J1911+77	2003hu		109.56	25.44	22484	22790	22364	37.61	140	3050	5
IC 4830	2001bt		337.32	-25.87	4388	4240	4392	34.13	72	111	2,3,4a
MCG +07-41-01	2002do		75.61	6.13	4761	5041	4578	34.54	154	65	5
PGC 63925	1990T		341.50	-31.52	11992	11809	11977	36.63	77	-972	1,3
IC 4919	1991ag	Grm15	342.55	-31.64	4264	4124	4246	34.07	78	106	1,2,3
Grm15	...	Grm15	341.85	-32.45	4286	4134	4269	34.36	78	-451	7
PavoI	...	PavoI	324.10	-32.58	4107	3916	4138	33.98	65	60	6
NGC 6928	2004eo		54.16	-17.26	4707	4855	4521	34.15	141	688	4a,b
NGC 6951	2000E		100.90	14.85	1424	1814	...	31.96	153	284	1,2,3
ESO 234-69	1992al		347.34	-38.49	4381	4242	4343	34.19	84	-2	1,2,3
NGC 6962	2002ha		47.41	-25.37	4211	4311	4035	34.10	134	238	5
NGC 6986	2002el		28.77	-35.67	8612	8591	8473	35.46	116	1038	2
2MASX J2120+44	2001fh		88.22	-3.81	3894	4185	3702	33.55	170	1016	5
Anon 2123-00	2006oa		51.74	-33.74	17988	18027	17810	37.35	135	425	5
Anon 2128-61	1992ae		332.70	-41.99	22484	22260	22479	37.76	76	1174	1,2,3
Anon 2135-62	1990af		330.82	-42.24	15080	14856	15079	36.90	75	440	1,2,3
NGC 7131	1998co		41.52	-44.94	5418	5419	5264	34.55	124	419	3
UGC 11816	2004ey		57.47	-38.27	4733	4804	4553	34.33	138	282	4b
Anon 2155-01	2006on		57.18	-40.55	20985	21009	20808	37.68	136	651	5
MDL59	...	MDL59	14.95	24.39	2567	2740	...	33.12	94	137	6
IC 5179	1999ee		6.50	-55.93	3422	3325	...	33.57	101	127	1,2,3,4a
UGC 12071	2006gr		90.75	38.36	10372	10689	10265	36.39	130	-792	4a
NGC 7311	2005kc		72.34	-43.41	4533	4612	4351	34.23	143	291	4b,5
UGC 12133	1998eg		76.48	-42.06	7423	7497	7238	35.46	146	-56	1,2,3
NGC 7329	2006bh		320.97	-45.79	3252	3058	...	33.63	71	-228	4b
Anon J2241-00	2006py		68.44	-48.79	17358	17372	17186	37.14	137	1333	4b
UGC 12158	2004ef		85.92	-33.43	9289	9413	9096	35.80	157	606	4b
IC 5270	1993L		5.94	-64.39	1983	1915	...	32.03	101	335	1,3
NGC 7448	1997dt		87.57	-39.12	2194	2338	...	32.99	152	-115	1,3
Anon 2304-37	1992aq		1.78	-65.31	30279	30107	30202	38.60	100	-285	1,2,3
MCG +05-54-41	2006en		98.23	-27.74	9575	9733	9387	36.00	164	97	5

Table 1—Continued

Galaxy (1)	SNe (2)	cluster (3)	GLON (4)	GLAT (5)	v_{hel} (6)	v_{220} (7)	v_{CMB} (8)	μ^0 (9)	Apex (10)	Δv_{220} (11)	Source (12)
NGC 7541	1998dh		82.84	-50.65	2689	2776	...	32.94	140	378	1,2,3
ESO 291-11	1992bl		344.15	-63.93	12891	12701	12839	36.64	92	-138	1,2,3
Pegasus	...	Pegasus	87.78	-48.38	3554	3633	3381	33.96	143	-188	6
NGC 7634	1972J	Pegasus	88.69	-47.93	3225	3317	...	33.53	144	177	1
NGC 7678	2002dp		98.88	-36.55	3489	3642	3308	33.65	155	325	5
A2634	...	A2634	103.45	-33.06	9409	9546	9230	35.72	157	1051	6
Anon 2340+26	1997dg	A2634	103.62	-33.98	10193	10321	10014	36.22	156	-317	1,2,3
A4038	...	A4038	25.19	-75.84	8994	8864	8904	35.82	106	-22	6
ESO 471-27	1993ah	A4038	25.87	-76.77	8803	8674	8714	35.70	106	256	1,3
NGC 7780	2001da		99.20	-52.06	5155	5214	4995	34.37	140	608	5
ESO 538-13	2005iq		64.83	-75.21	10206	10110	10097	36.15	114	-199	4a,b

Table 2. MEAN RANDOM (ABSOLUTE) MODULUS DIFFERENCES BETWEEN DIFFERENT SOURCES

	WAN-REI (1)	JHA-REI (2)	WOO-REI (3)	WAN-JHA (4)	WAN-WOO (5)	JHA-WOO (6)	FRE-WOO (7)	SNe-cl. (8)
$\sigma_{(m-M)}:$	0.09	0.14	0.16	0.12	0.20	0.20	0.14	0.18
N:	81	101	7	88	15	15	6	14

Table 3. PROPERTIES OF THE HUBBLE DIAGRAMS FROM DIFFERENT SOURCES

Sample (1)	N (2)	slope a (3)	error $\epsilon(a)$ (4)	$\sigma_{(m-M)}$ (5)
Reindl	62	0.188	0.004	0.16
Wang	55	0.190	0.003	0.13
Jha	72	0.183	0.003	0.18
Wood-Vasey/Freedman	45	0.189	0.005	0.16
Hicken	88	0.194	0.004	0.16
Masters	27	0.208	0.007	0.14
Jørgensen	10	0.179	0.014	0.18
all	218	0.193	0.002	0.15

Table 4. MODULUS DIFFERENCES $\Delta(m - M)_{\text{model}}$ BETWEEN DIFFERENT WORLD MODELS AND THE MODEL WITH $\Omega_M = 0.3$, $\Omega_\Lambda = 0.7$ ($q_0 = -0.55$) IN FUNCTION OF z

z (1)	$\log z$ (2)	$\Delta(m - M)_{\text{model}}$					
		$\Omega_\Lambda = 0.4$ (3)	$\Omega_\Lambda = 0.9$ (4)	$q_0 = 0.00$ (5)	$q_0 = -0.20$ (6)	$q_0 = -0.80$ (7)	$q_0 = -1.00$ (8)
0.01	-2.000	0.00	-0.00	0.01	0.00	-0.00	-0.00
0.02	-1.699	0.01	-0.01	0.01	0.01	-0.01	-0.01
0.03	-1.523	0.01	-0.01	0.02	0.01	-0.01	-0.01
0.04	-1.398	0.02	-0.01	0.02	0.02	-0.01	-0.02
0.05	-1.301	0.02	-0.02	0.03	0.02	-0.01	-0.02
0.06	-1.222	0.03	-0.02	0.04	0.02	-0.02	-0.03
0.07	-1.155	0.03	-0.02	0.04	0.03	-0.02	-0.03
0.08	-1.097	0.04	-0.03	0.05	0.03	-0.02	-0.04
0.09	-1.046	0.04	-0.03	0.05	0.03	-0.02	-0.04
0.10	-1.000	0.05	-0.03	0.06	0.04	-0.03	-0.05

Table 5. CONVERGENCE DEPTH OF THE LOCAL SUPERCLUSTER.

Author(s)	Method	N	convergence (km s^{-1})
Aaronson et al. 1986	clusters (21cm)	10	< 10,000
Lilje et al. 1986	21cm	field galaxies	~ 4000
Jerjen & Tammann 1993	clusters	15	< 6400
Federspiel et al. 1994	line widths	field galaxies	4000
Riess et al. 1995	SNe Ia	13	< 7000
Giovanelli et al. 1998	clusters (21cm)	24	< 6000
Dale et al. 1999	clusters (21cm)	52	4000-6000
Hoffman et al. 2001	various	field galaxies	< 6000
Watkins et al. 2009	various	field galaxies	5000
present paper	SNe Ia, clusters	170	3500 ± 300

Table 6. ONE-DIMENSIONAL BULK VELOCITIES OF (SUPER-) CLUSTERS AND GROUPS
WITH $3300 < v_{\text{CMB}} < 10,000 \text{ km s}^{-1}$

cluster (1)	μ^0 (2)	N (3)	v_{CMB} (4)	v_{model} (5)	$v_{\text{CMB}} - v_{\text{model}}$ (6)
A2806	35.47	1	8310	7588	722 ± 623
N383Gr	34.54	2	4957	4977	-20 ± 248
A2877	35.46	1	7396	7554	-158 ± 555
N507Gr	34.31	2	4802	4482	319 ± 240
A0194	34.60	2	5302	5115	187 ± 265
A0262	34.44	1	4770	4756	14 ± 358
A0397	35.87	2	9749	9089	660 ± 487
A0400	35.19	1	7276	6685	591 ± 546
A0426	34.68	2	5745	5304	441 ± 287
A0496	36.03	1	9928	9767	160 ± 745
A0539	35.95	1	8580	9422	-842 ± 643
A0569	34.92	3	6053	5915	138 ± 303
A0634	35.72	1	7957	8495	-538 ± 597
Cancer	34.51	2	4623	4910	-286 ± 231
A0779	35.52	1	6840	7761	-921 ± 513
Hydra	34.23	2	3973	4322	-349 ± 199
AS639	34.89	1	6512	5835	677 ± 488
A1367	34.98	2	6707	6078	629 ± 335
Coma	35.49	3	6982	7657	-675 ± 349
A3574	34.42	3	4913	4713	200 ± 246
AS753	34.27	1	4306	4401	-95 ± 323
A2199	35.81	2	8949	8847	103 ± 447
PavoII	34.28	2	4189	4422	-233 ± 209
Grm15	34.22	2	4269	4302	-34 ± 213
PavoI	33.98	1	4138	3857	281 ± 310
Pegasus	33.75	2	3381	3472	-91 ± 169
A2634	35.97	2	9230	9507	-278 ± 461
A4038	35.76	2	8904	8649	255 ± 445




Fig. 1.— a)–g) Hubble diagrams from eight different sources shifted to a common value of H_0 (Here $H_0 = 62.3$). The two values of N give the number of objects with $3000 < v_{220}/\text{CMB} < 20,000 \text{ km s}^{-1}$ (closed symbols) and those outside this range (open symbols). Two SNe Ia with $(m - M) < 30.0$ are not shown. The solid slightly curved line, defined by equation (1), holds for a flat $\Omega_M = 0.3$, $\Omega_\Lambda = 0.7$ model. h) The combined Hubble diagram from a)–g); objects with more than one distance determination are plotted at the mean distance. The increasing scatter below $(m - M) \sim 33.0$ is a clear effect of the relative importance of peculiar velocities at small redshifts.




Fig. 2.— A combined Hubble diagram of 176 galaxies with TRGB distances (green) and 30 galaxies with Cepheid distances (blue); the data for the SNe Ia and clusters are repeated from Figure 1h. For the zero-point normalization of the distance moduli ($m - M$) see text. The velocities are corrected for Virgocentric infall and in case $v_{220} > 3500 \text{ km s}^{-1}$ for the CMB correction. The Virgo (square) and Fornax (diamond) clusters are plotted at their derived mean values $(m - M) = 31.52$ and 31.65 and $v_{220} = 1152$ and 1371 , respectively, from Tammann et al. (2008b). The fitted, slightly curved full drawn Hubble line corresponds to a Λ CDM model with $\Omega_M = 0.3$, $\Omega_\Lambda = 0.7$.




Fig. 3.— Hubble diagram from $D_n - \sigma$ distances (Faber et al. 1989). If the value of H_0 is assumed to be 62.3 at $(m - M) = 31.5$ it decreases to $H_0 = 56.1$ at $(m - M) = 35.0$. The dashed line holds for a constant value of H_0 .




Fig. 4.— Hubble diagram from SBF distances (Tonry et al. 2001). The published distances give $H_0 = 62.5$ at $(m - M) = 30.0$ and $H_0 = 78.7$ at $(m - M) = 33.0$. The dashed line holds for a constant value of H_0 .




Fig. 5.— Hubble diagram from PNLF distances. The published distances give $H_0 = 62.9$ at $(m - M) = 29.0$ and $H_0 = 82.1$ at $(m - M) = 31.5$. The dashed line holds for a constant value of H_0 . The open symbols are not used for the fit.




Fig. 6.— Panel a): The deviations $\Delta \log v$ from the adopted Hubble line of the objects in Figure 2 are plotted versus distance modulus. The full drawn line is a regression to all points. Note its flatness, allowing the average value of H_0 to vary systematically as a function of distance by not more than 2.3% (1σ) over a distance interval of a factor of 100. Symbols as in Figure 2. Panel b): same as a), but the distances of objects within 0.50 mag bins have been averaged. Any deviations from the adopted Hubble line are hardly significant. Error bars are only shown if they are larger than the symbols. Bins with less than 5 elements are shown as open symbols. The arrow at $(m - M) = 35.3$ (corresponding to $v \sim 7200 \text{ km s}^{-1}$) is where Zehavi et al. (1998) and Jha et al. (2007) have suggested a drop of H_0 by 6.5% (the so-called “Hubble Bubble”) which is denied by the present data. The histogram at the bottom of the diagram shows the number of objects per bin.




Fig. 7.— The modulus differences $\Delta(m - M)$ vs. the model-independent value of $\log z$ for different trial models as compared to the standard model specified by $(\Omega_M, \Omega_\Lambda) = (0.3, 0.7)$ or $q_0 = -0.55$. The full curved lines correspond to two flat models with $(\Omega_M, \Omega_\Lambda) = (0.6, 0.4)$ and $(0.1, 0.9)$, respectively. The dashed lines stand for four models specified by only $q_0 = 0.00, -0.20, -0.80$, and -1.00 (top to bottom). Running means of the data from Figure 6 are shown for intervals of $\log z = 0.3$ in steps of $\Delta \log z = 0.1$. The histogram shows the number of objects per $\log z$ interval of 0.1.




Fig. 8.— A hypothetical Hubble diagram in case that neighboring galaxies were in rest with the CMB radiation and had no streaming motion towards the apex of the CMB. In that case the galaxies would occupy the space between the two curved envelopes. The observed galaxies within $\sim 1000 \text{ km s}^{-1}$ center strongly towards the center line of the diagram, have hence small peculiar velocities and must share the Galactic CMB motion. The simple test fails beyond $\sim 1000 \text{ km s}^{-1}$. Small dots are the objects of Figure 2. Red and blue points lie within 30 degrees from the apex and antapex, respectively; in the hypothetical case they would lie near to the envelope lines.




Fig. 9.— Velocity residuals $\Delta \log v_{220}$ from Table 1 in function of $\cos(\alpha)$, where α is the angle away from the CMB apex A_{corr} , for a) $500 < v_{220} < 3500$ and b) $3500 < v_{220} < 7000$ km s⁻¹. Galaxies with $v_{220} < 3500$ move coherently within the Local Supercluster. Galaxies with $v_{220} > 3500$ reflect a systematic velocity of the Local Supercluster of 448 ± 73 km s⁻¹ toward the CMB apex A_{corr} . The velocity agrees with 495 ± 25 km s⁻¹ as derived from the CMB data. Objects within 30° from the apex (antapex) are shown in red (blue). The dashed line in panel b) holds for objects in rest relative to the CMB. Symbols as in Figure 8.




Fig. 10.— Same as Figure 9, but for velocity intervals with a width of only 1000 km s^{-1} and plotted every 200 km s^{-1} . The expected asymptotic apex velocity of 495 km s^{-1} is reached in panel d) or e), i.e. at $v_{220} = 3500 \text{ km s}^{-1}$.




Fig. 11.— An Aitoff projection in Galactic coordinates of the objects with $3500 < v_{\text{CMB}} < 7000$. Objects with residual velocities $\Delta v < 150 \text{ km s}^{-1}$ are shown in red, those with $\Delta v > 150 \text{ km s}^{-1}$ in blue. Objects with residuals $-150 < \Delta v < 150 \text{ km s}^{-1}$ are shown as open symbols. The positions of the corrected apex and antapex (after subtraction of the Virgocentric infall vector of the LG) as well as of the Great Attractor (GA) and the Shapley Concentration (SC) are indicated.




Fig. 12.— Flow diagram of the velocity residuals $\Delta v_{220} = v_{220} - v_{\text{model}}$, projected on the “apex plane” (see text), of all objects with $|\beta| < 45^\circ$ and $500 < v_{220} < 10,000 \text{ km s}^{-1}$. The distance scale is shown by the concentric circles separated by 1000 km s^{-1} . The velocity residuals are to the same scale. The dashed circle at 3500 km s^{-1} denotes the boundary of the Local Supercluster. The bulk motion of the Local Supercluster causes velocity residuals that are conceived by the observer as “infall” (red arrows) and “outflow” (blue arrows). The probabilities P that the distribution of red and blue arrows is the result of chance is shown for the 45° sectors about the CMB apex and antapex.